

Answers/Clarifications of issues from the Pre-Bid Meeting held on May 03, 2022.

Please make the following changes in the specifications for the referenced project:

1. Page IV-2

REMOVE: c. Remove and replace concrete apron around discharge box. Approximately thirty (30) SF, being carefully not to damage discharge box.

ADD: c. Remove and replace entire concrete apron around discharge box. Approximately one hundred twenty (120) SF, being carefully not to damage discharge box.

2. Page IV-4, 2 Specific-e

REMOVE: Concrete Pad: Approximately three (3') foot by ten (10') foot area, four inches (4") thick. Reinforced with WWF to prevent cracking.

ADD: Concrete Pad: Approximately three (3') foot wide, four inches (4") thick walkway around a ten (10') foot long by six (6")foot wide discharge box, Reinforced with WWF to prevent cracking.

3. Page IV-6 Specific- f

REMOVE: f. Remove right side of concrete skirt where the Murdock hydrant is located about approximately thirty (30) SF of concrete pad. Make sure all cuts are clean and square to adjoining skirt areas. Exact location shall be marked with spray paint by the Project Manager.

ADD: f. Remove the three (3')foot wide concrete skirt / pad around concrete discharge box, careful not to damage existing concrete discharge box.

4. Page IV-6 Specific- k

REMOVE: k. Replace concrete apron around discharge box. Approximately thirty (30) SF of area. By installing 2" x 4" wood form work at prior to concrete

ADD: k. Replace concrete apron around discharge box. Approximately one hundred twenty (120) SF of area. By installing 2" x 4" wood form work at prior to concrete

5. Page IV-7 Specific- m.

REMOVE: m. Tie in a new slab by drilling into the edge of the existing slab at least four inches, and grout in short lengths of rebar, which will extend into the new slab.

Questions arising from Pre-Bid meeting:

Q: Location of the Gaskets are where?

A: Current conditions does not allow to see the gaskets they are located on the sliding gate valve that is currently under water wit the pond being full. The Pond will be empty at the time of the work to be done.

The Pre-bid meeting minutes and Sign-in sheet are made part of this addendum.

Please use the attached **REVISED BID FORM** when submitting your Bid.

-END OF ADDENDUM NO. 1-