
MARLAY-TAYLOR WATER RECLAMATION FACILITY ST. MARY'S COUNTY, MARYLAND SECONDARY CLARIFIER NO. 1 REPLACEMENT

GENERAL NOTES:

- 1. ALL WATER AND SEWER CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE ST. MARY'S COUNTY METROPOLITAN COMMISSION (METCOM) STANDARD CONSTRUCTION DETAILS AND TECHNICAL SPECIFICATIONS.
- 2. CONTRACTOR SHALL CONTACT THE ENGINEERING DEPARTMENT, ST. MARY'S COUNTY METROPOLITAN COMMISSION, FORTY-EIGHT (48) HOURS PRIOR TO START OF CONSTRUCTION. PHONE NUMBER 301-737-7400. CONTRACTOR TO ALSO CONTACT THE ENGINEERING DEPARTMENT BEFORE RESTARTING WORK AFTER WORK HAS STOPPED FOR MORE THAN FIVE DAYS.
- 3. THE CONTRACTOR SHALL NOTIFY MISS UTILITY AT (800) 257-7777 AT LEAST 48 HOURS PRIOR TO ANY EXCAVATION.
- 4. ALL CONNECTIONS TO EXISTING UTILITIES BUILT BY OTHERS SHALL BE PERFORMED UNDER THIS CONTRACT.
- 5. THE LOCATIONS OF UNDERGROUND UTILITIES AS SHOWN HEREON ARE BASED ON ABOVE GROUND FIELD OBSERVATIONS, MISS UTILITY PAINT MARKINGS, AND RECORD DRAWINGS. ADDITIONAL BURIED UTILITIES OR STRUCTURES MAY BE ENCOUNTERED. NO EXCAVATIONS WERE MADE DURING THE PROGRESS OF THIS SURVEY TO LOCATE BURIED UTILITIES/STRUCTURES. ALL SUBSURFACE UTILITIES/STRUCTURES SHOWN ARE TO BE CONSIDERED APPROXIMATE LOCATION ONLY. UNDERGROUND UTILITIES MUST BE VERIFIED BY TEST PITS AND PROTECTED DURING CONSTRUCTION. IN CASE OF BREAKAGE OF ANY EXISTING SEWER PIPE, RESULTANT SEWAGE OVERFLOW AND/OR SPISHALL IMMEDIATELY BE REPORTED TO THE OWNER. THE CONTRACTOR SHALL BE LIABLE FOR ALL SEWAGE OVERFLOW AND/OR SPILL CLEAN UP COSTS INCURRED BY THE OWNER AND/OR STATE OF MARYLAND.
- 6. THE CONTRACTOR SHALL PROTECT ALL TREES FROM DAMAGE BEYOND THE LIMITS OF DISTURBANCE. ANY DAMAGE SHALL BE RECTIFIED TO THE SATISFACTION OF THE OWNER.
- 7. CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ALL PERMITS, INCLUDING BUT NOT LIMITED TO GROUNDWATER APPROPRIATION PERMITS NECESSARY FOR CONSTRUCTION. CONTRACTOR SHALL NOTIFY THE OWNER AND ENGINEER OF ANY CHANGES OR CONDITIONS REQUIRED BY ANY PERMIT.
- 8. THESE DRAWINGS WERE PREPARED BASED ON AS-BUILT AND OTHER CONSTRUCTION DOCUMENTS, WHICH MAY OR MAY NOT BE COMPLETELY ACCURATE. SCALING OF THESE DRAWINGS SHALL BE FOR ESTIMATING PURPOSES ONLY AND ALL DIMENSIONS SCALED SHALL BE CONSIDERED APPROXIMATE AND SHALL BE FIELD VERIFIED.
- 9. CONSTRUCTION SHALL CONFORM TO ALL APPLICABLE FEDERAL, STATE AND LOCAL LAWS, REGULATIONS, STANDARDS, SPECIFICATIONS AND REQUIREMENTS.
- 10. HORIZONTAL CONTROL IS BASED ON MARYLAND STATE PLANE SYSTEM NAD 83/91. VERTICAL CONTROL IS BASED ON NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88).
- 11. CONTRACTOR SHALL NOT TAP OR OTHERWISE PENETRATE EXISTING WATER OR SEWER LINES WITHOUT PRIOR APPROVAL FROM METCOM. CONTRACTOR IS RESPONSIBLE TO AVOID SPILLAGE OF RAW SEWAGE. CONTRACTOR SHALL PROVIDE ALL SEWER PLUGGING AND PUMPING EQUIPMENT NECESSARY TO AVOID SPILLAGE.
- 12. A PRE-CONSTRUCTION MEETING IS REQUIRED PRIOR TO START OF CONSTRUCTION. MATERIALS DELIVERED TO THE SITE FOR WATER AND SEWER CONSTRUCTION MUST BE INSPECTED BY THE OWNER PRIOR TO START OF WORK.
- 13. MANIPULATION OF VALVES BY ANY PARTY OTHER THAN REPRESENTATIVES OF METCOM IS PROHIBITED.
- 14. EXISTING FEATURES DENOTED BY SLANTED TEXT
- 15. EXISTING CONDITIONS DATA TAKEN FROM 1981 BEAVIN CO. PLANS, 1996 BUCHART—HORN PLANS, EBA SURVEY DATED AUGUST 2019.
- 16. THE CONTRACTOR SHALL REPAIR OR REPLACE IN KIND ANY EXISTING FEATURES DAMAGED DURING CONSTRUCTION.
- 17. ALL CONSTRUCTION MUST BE DONE IN COMPLIANCE WITH THE OCCUPATION SAFETY AND HEALTH ACT, LATEST EDITION, AND ALL RULES AND REGULATIONS THERETO.
- 18. THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF ALL PERMITS SECURED, WHICH TAKE PRECEDENCE OVER SPECIFICATIONS.



VICINITY MAP

SCALE: 1"=2,000'

Map Copyright ADC The Map People (800) 829—6277 Permit use No.: 21003214 Expiration: 03/31/2021



LOCATION MAP SCALE: 1"=200'

SHEET INDEX

SHEET NO.	NO.	TITLE
1 2 3	G-2	TITLE SHEET, SHEET INDEX, GENERAL NOTES ABBREVIATIONS AND LEGEND
3	C-1	EXISTING SITE PLAN AT SECONDARY CLARIFIER NO. 1, LIMIT OF WORK, AND
4 5	C-2	PROPOSED SECONDARY CLARIFIER NO. 1, PIPING PLAN AND PROFILE
5	C-3	OVERALL SITE PLAN
6 7	D-1	DEMOLITION-SECONDARY CLARIFIER NO. 1
/		EROSION AND SEDIMENT CONTROL PLAN
8	ES-2	
9	ES-3	
10	S-1	
11 12	S-2 S-3	
13	S-4	PILE LOCATION AND GRADE BEAM LAYOUT
14		FOUNDATION SLAB PLAN AND REINFORCING LAYOUT PLAN AND DETAILS
15	S-6	SECTIONS AND DETAILS
16	S-7	SECTIONS AND DETAILS
17	S-8	SECTIONS AND DETAILS
18		TYPICAL GRADE BEAM AND PILE DETAILS
19		EX STEEL TRUSS BRIDGE AND MECHANISM PLAN, SECTIONS AND DETAILS
20		TYPICAL STRUCTURAL DETAILS
21		SECONDARY CLARIFIER NO. 1 PLAN AND DETAILS
22	PM-2	
23		ELECTRICAL ABBREVIATIONS, SYMBOLS, NOTES AND EXISTING SITE PLAN
24	E-2	
25	E-3	DUCT BANK CROSS SECTIONS AND CONDUIT SCHEDULE
26	E-4	SECONDARY CLARIFIER NO. 1 ELECTRICAL DEMOLITION PLAN
27	E-5	SECONDARY CLARIFIER NO. 1 ELECTRICAL PLAN

OWNER'S CERTIFICATIONS:

I HEREBY CERTIFY THAT ALL CONSTRUCTION WILL BE IN ACCORDANCE WITH THE ST. MARY'S COUNTY METROPOLITAN COMMISSION'S DESIGN MANUAL AND THESE PLANS AS APPROVED.

BLOWER/CHEMICAL BUILDING ELECTRICAL PLAN AND ONE-LINE DRAWINGS

Man C Hellal 5-18-21

CHRISTY HOLLANDER, PE, CHIEF ENGINEER
ST. MARY'S COUNTY METROPOLITAN COMMISSION

DATE

I HEREBY CERTIFY THAT ANY CLEARING, GRADING, CONSTRUCTION, DEVELOPMENT, OR ALL OF THESE WILL BE DONE PURSUANT TO THIS PLAN AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF TRAINING AT A MARYLAND DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM BEFORE BEGINNING THE PROJECT.

CHRISTY HOLLANDER, PE, CHIEF ENGINEER
ST. MARY'S COUNTY METROPOLITAN COMMISSION

5-18-21

DATE

SCD INFORMATION BLOCK:

TOTAL DISTURBED AREA: 0.90 AC.
DISTURBED AREA WITHIN PUBLIC R/W: 0.00 AC.
DISTURBED AREA OUTSIDE PUBLIC R/W: 0.90 AC.
AREA TO BE VEGETATIVE STABILIZED: 0.70 AC.
VOLUME OF CUT: 4,300 CY
VOLUME OF FILL: 3,800 CY
SPOIL: 500 CY

* ESTIMATES OF EARTHWORK QUANTITIES ARE PROVIDED SOLELY FOR THE PURPOSE OF DETERMINING PERMITTING REQUIREMENTS. SINCE FINAL EARTHWORK QUANTITIES ARE BASED ON MANY VARIABLE CONDITIONS OVER WHICH THE ENGINEER HAS NO CONTROL, INCLUDING VARIABILITY OF SOILS, ALLOWABLE SURVEY, CONSTRUCTION TOLERANCES, AND COMPACTION RATES. THE ENGINEER CANNOT GUARANTEE THE ACCURACY OF THE ESTIMATES OF FINAL CONSTRUCTION. THE OWNER/DEVELOPER SHOULD REQUIRE THE CONTRACTOR TO PROVIDE THEIR OWN ESTIMATES OF THE QUANTITIES IN THEIR RESPECTIVE BID.

ST. MARY'S SOIL CONSERVATION DISTRICT

D SOIL BORING LOCATIONS

St. Mary's
Soil Conservation District
Plan Sheets /-5 o f 5
Approved 5 126 1202/
By
Plan expires 2 years from approval date

The Limits of Grading equal the Limits of Disturbance as shown on Sheet #ES-01

ST. MARY'S COUNTY
Dept. Public Works & Transportation
Date Approved: 06-15-202
Approval Reference
Approved By:

HAND A STANDARD OF STANDARD OF

T THESE DOCUMENTS WERE PREPARED OR THAT I AM A DULY LICENSED PROFESSIONAL HE LAWS OF THE STATE OF MARYLAND, 120, EXPIRATION DATE: 4/20/2023
RUMMEL, KLEPPER & KAHL, LLP 700 EAST PRATT STREET, SUITE 500

DESCRIPTION

BY DATE

REVISIONS

Y METROPOLITAN COMMISSION LIFORNIA, MD 20619 (301) 737-7400 ET INDEX, GENERAL NOTES

ST. MARY'S COUNTY M 23121 CAMDEN WAY, CALIFC TITLE SHEET, SHEET

ENGINEER DESIGNED BY
RJA MLT
DRAWN BY DATE
DED 4/2021
PROJECT NUMBER
8191SR

DRAWING NUMBER

G — 1

SHEET NO. 1 OF 28

<u>ABBREVIA</u>		<u>ABBREVI</u>	ATIONS (CONTINUED)		ATIONS (CONTINUED)		TIONS (CONTINUED)
AB ABAN	ANCHOR BOLT ABANDONED	E EA	EAST EACH	M MAN	MOTOR MANUAL	STR SUP	STRUCTURAL SUPPLY
Ac.	ACRE	ECC	ECCENTRIC	MAS	MASONRY	SUSP	SUSPENDED
ADJ AFF	ADJUSTABLE, ADJACENT	EF	EACH FACE, EXHAUST FAN	MATL MAX	MATERIAL MAXIMUM	SV	SHUTOFF VALVE
ALT	ABOVE FINISHED FLOOR ALTERNATE, ALTERNATIVE	EJ EL	EXPANSION JOINT ELEVATION	MC	MECHANICAL COUPLING	SYS	SYSTEM
ALUM	ALUMINUM	ELEV	ELEVATION	MCC	MOTOR CONTROL CENTER	T&B	TOP AND BOTTOM
ANC APPROX	ANCHOR APPROXIMATE	ELL EMER	ELBOW EMERGENCY	MECH MED	MECHANICAL MEDIUM	TBM TDH	TEMPORARY BENCH MARK TOTAL DYNAMIC HEAD
ARCH	ARCHITECTURAL	ENCL	ENCLOSURE	MFR(S)	MANUFACTURER(S)	TEL	TELEPHONE
ASSY	ASSEMBLY	ENT	ENTRANCE	MG	MILLION GALLONS	TEMP	TEMPERATURE, TEMPORARY
ATS AUTO	AUTOMATIC TRANSFER SWITCH AUTOMATIC	EOP EQ	EDGE OF PAVEMENT EQUAL	MGD MH	MILLION GALLONS PER DAY MANHOLE	THK TOC	THICK, THICKNESS TOP OF CONCRETE
AUX	AUXILIARY	EQUIP	EQUIPMENT	MIN	MINIMUM, MINUTE	TOG	TOP OF GRATE
AWG	AMERICAN WIRE GAUGE	EW	EACH WAY	MISC	MISCELLANEOUS	TOM	TOP OF MASONRY
В	BEAM, BORING	EWEF EXH	EACH WAY EACH FACE EXHAUST	MJ MJRG	MECHANICAL JOINT MECHANICAL JOINT RETAINER GLAND	TOR TOS	TOP OF RIM TOP OF STEEL
ВТОВ	BACK TO BACK	EX	EXISTING	MJTR	MECHANICAL JOINT WITH TIE ROD	TRAV	TRAVERSE
BF	BLIND FLANGE	EXP	EXPANSION, EXPOSED	MK	MARK NUMBER	TS	TUBE STEEL
BHP BITUM	BRAKE HORSEPOWER BITUMINOUS	EXPJT EXT	EXPANSION JOINT EXTENSION, EXTERNAL	MO MOD	MASONRY OPENING, MOTOR OPERATED MOTOR OPERATED DAMPER	TYP	TYPICAL
BK	BACK			MTL	MATERIAL	UH	UNIT HEATER
BLDG BLK	BUILDING BLOCK	FB FCA	FACE BRICK FLANGED COUPLING ADAPTER	MVMCC	MEDIUM VOLTAGE MOTOR CONTROL CENTER	UNO UNREINF	UNLESS NOTED OTHERWISE UNREINFORCED
BLKG	BLOCKING	FCO FCO	FLOOR CLEANOUT	Ν	NORTH	USGS	UNITED STATES GEOLOGICAL SURVEY
BLT(S)	BOLT(S)	FD	FLOOR DRAIN	NA	NOT APPLICABLE		
ВМ	BENCHMARK	FE FEC	FIRE EXTINGUISHER FIRE EXTINGUISHER CABINET	NC N.I.C	NORMALLY CLOSED NOT IN CONTRACT	V VAC	VALVE, VOLT VACUUM
BMP BOF	BEST MANAGEMENT PRACTICES BOTTOM OF FOOTING	FEC	FIRE EXTINGUISHER CABINET FINISHED FLOOR	N.I.C NO	NOT IN CONTRACT NORMALLY OPEN	VAC	VACOUM VITRIFIED CLAY PIPE
ВОТ	BOTTOM	FTOF	FACE TO FACE	NO.(S)	NUMBER(S)	VERT	VERTICAL
BRG BRK	BEARING BRICK	FIG FIN	FIGURE FINISH	NOM	NOMINAL	VT VTR	VITRIFIED TERRA COTTA VENT THROUGH ROOF
BS BS	BOTH SIDES	FINGR	FINISH GRADE	NPT NPW	NATIONAL PIPE THREAD NONPOTABLE WATER	V IIX	
BSMT	BASEMENT	FL	FLOOR, FLOW LINE	NTS	NOT TO SCALE	W	WEST, WIDTH, WATER
B&S BTU	BELL AND SPIGOT BRITISH THERMAL UNIT	FLASH FLEX	FLASHING FLEXIBLE	00	ON CENTER	W/ WHC	WITH WATER HOUSE CONNECTION
BTUH	BRITISH THERMAL UNIT—HOUR	FLG	FLANGE, FLASHING	OC OH	ON CENTER OVERHEAD	WI	WROUGHT IRON
BTWN	BETWEEN	FM	FORCE MAIN, FLOW METER	OPER	OPERATING	WL	WATER LEVEL
C/EJ	CONTRACTION/EXPANSION JOINT	FND FOM	FOUNDATION FACE OF MASONRY	OPNG OPP	OPENING OPPOSITE, OPPOSING	WM W/O	WATER METER WITHOUT
C/M	CIVIL/MECHANICAL	FRP	FIBERGLASS REINFORCED PLASTIC OR POLYESTER	OFF	OFFOSITE, OFFOSING	W/O WT	WATERTIGHT
CFM	CUBIC FEET PER MINUTE	FT FTG	FEET, FOOT FOOTING	Ρ	PUMP	WV	WATER VALVE
C&G CHB	CURB AND GUTTER CHORD BEARING	FWD	FORWARD	PAV PCCP	PAVEMENT PRESTRESSED CONCRETE CYLINDER PIPE	WWF WZTC	WELDED WIRE FABRIC WORK ZONE TRAFFIC CONTROL
CHKD	CHECKERED	F&F	FLANGE & FLARE	PCF	POUNDS PER CUBIC FOOT	WZTO	WORK ZONE HVALLIO CONTROL
CHKDPL	CHECKERED PLATE	GA	GAUGE	PE	PLAIN END	X	BY, TIMES
CHL CI	CHORD LENGTH CAST IRON	GAB	GRADED AGGREGATE BASE	PH PJ	PIPE HANGER PUSH ON JOINT	YD	YARD
CIMH	CAST IRON MANHOLE	GAL	GALLON	PK	PK NAIL	10	
CIMHS	CAST IRON MANHOLE STEPS	GALV GEN	GALVANIZED GENERAL, GENERATOR	PL PL XWD	PLATE	&	AND
CIP CISP	CAST IRON PIPE CAST IRON SOIL PIPE	GPM	GALLONS PER MINUTE	PLYWD PNL(S)	PLYWOOD PANEL(S)	۷ ۵	ANGLE (STEEL) AT
CJ	CONTRACTION JOINT	GR	GRADE	POL	POINT ON LINE	Ç	CENTERLINE
CJT	CONTROL JOINT	GV GWB	GATE VALVE, GRAVITY VENTILATOR GYPSUM WALLBOARD	PR	PAIR	C	CHANNEL (STEEL)
CL CLG	CLASS CEILING	GYP	GYPSUM	PREFAB PROP	PREFABRICATED PROPOSED	# %	NUMBER PERCENT
CLR	CLEAR, CLEARANCE	1.1	ACCESS HATCH	PS	PIPE SUPPORT	/0	PERCENT
CMP	CORRUGATED METAL PIPE	H HA	ACCESS HATCH HYDRAULIC ACTUATOR	PSF	POUNDS PER SQUARE FOOT		
CMU CO	CONCRETE MASONRY UNIT CLEAN OUT, COMPANY	HALCP	HYDRAULIC ACTUATOR LOCAL CONTROL PANEL	PSI PT	POUNDS PER SQUARE INCH POINT		SECTION
COL	COLUMN	НАМСР НВ	HYDRAULIC ACTUATOR MAIN CONTROL PANEL HOSE BIBB	PV	PLUG VALVE	DRAWING	NUMBER OR
COMB COMP	COMBINATION COMPRESSOR, COMPRESSED	HD	HEAD	PVC P.V.C	POLYVINYL CHLORIDE POINT OF VERTICAL CURVE	NUMBER WHERE	DETAIL LETTER
CONC	CONCRETE	HF	HOSE FAUCET	P.V.I	POINT OF VERTICAL INTERSECTION	SECTION OR	00 00
CONN	CONNECTION	HGT HLU	HEIGHT HAND LAY—UP	P.V.T	POINT OF VERTICAL TANGENT	DETAIL IS TAKEN	DRAWING NUMBER WHERE SECTION OR
CONST CONT	CONSTRUCTION CONTINUOUS, CONTINUATION, CONTROL	HM	HOLLOW METAL	PW	POTABLE WATER	INDICATES	DETAIL APPEARS
COR	CORNER	HMA	HOT MIX ASPHALT	QTR	QUARTER	DIRECTION OF CUTTING PLANE -	
CORR	CONFR. CORRUGATED	HMC HMJ	HARNESSED MECHANICAL COUPLING HARNESSED MECHANICAL JOINT	D	PADILIC DICED		
COV CPLG	COVER COUPLING	HOA	HAND OFF AUTO	R RCP	RADIUS, RISER REINFORCED CONCRETE PIPE		
CRS	COURSES, CORROSION-RESISTANT STEEL	HORZ HP	HORIZONTAL HIGH POINT, HORSEPOWER	RCCP	REINFORCED CONCRETE CYLINDER PIPE		
CSJ CSK	CONSTRUCTION JOINT COUNTERSUNK	HP HR	HOUR, HANDRAIL	RED REF	REDUCER, REDUCING REFERENCE		
CTOC	CENTER TO CENTER	HSS	HOLLOW STRUCTURAL STEEL	REINF	REINFORCED, REINFORCING		
CTR(S)	CENTER(S)	HV HVAC	HOSE VALVE HEATING, VENTILATING AND AIR CONDITIONING	REM	REMOVABLE		
CV CV	CUBIC CHECK VALVE	HW	HOT WATER	REQD REV	REQUIRED REVISION, REVISED		
CUYD	CUBIC YARD	HWY	HIGHWAY	RFF	REINFORCED FABRIC FENCE		
		HYD	HYDRANT	RG BM	RETAINER GLAND		
D DBL	DOOR, DRAIN, DAMPER DOUBLE	ID	INSIDE DIAMETER, INLET DAMPER	RM ROW	ROOM RIGHT-OF-WAY		
DEG	DEGREE	IF	INSIDE FACE	RPM	REVOLUTIONS PER MINUTE		
DEPT	DEPARTMENT	IN INC	INCH, INCHES INCORPORATED	R/W	RIGHT-OF-WAY		
DH DI	DOOR HEIGHT DROP INLET, DUCTILE IRON	INCL	INCLUDING	S	SOUTH, SPEAKER		
DIA	DIAMETER	INCR INSUL	INCREASE, INCREASING, INCREASER INSULATE, INSULATION, INSULATING	SAN	SANITARY		
DIM DIP	DIMENSION DUCTILE IRON PIPE	INV	INVERT	SCADA SCE	SUPERVISORY CONTROL AND DATA ACQUISITION STABILIZED CONSTRUCTION ENTRANCE		
DISCH	DISCHARGE	V	NIDC	SCH	SCHEDULE		
DIV	DIVISION	K KSI	KIPS KIPS PER SQUARE INCH	SD	STORM DRAIN		
DN DO	DOWN DOOR OPENING	KW	KILOWATT	SEC SECT	SECOND SECTION		
DPR	DAMPER	KWH	KILOWATT HOUR	SF	SQUARE FOOT, SUPPLY FAN		
DR	DRAIN	L	LOUVER, LENGTH	SG	SLUICE GATE		
DS DWG(S)	DOWNSPOUT DRAWING(S)	LB(S)	POUND(S)	SHT SIM	SHEET SIMILAR		
DWG(3) DWL(S)	DOWEL(S)	LF	LINEAR FEET	SPA	SPACING, SPACES		
· /	· ·	LG LIC	LENGTH, LONG LICENSE	SPEC(S)	SPECIFICATION(S)		
		LIN	LINEAL, LINEAR	SQ SS	SQUARE STAINLESS STEEL, SANITARY SEWER		
					Similar Of the Control of the Contro		
		LOC	LOUVER OPENING	STA	STATION		
		LO LOC LP	LOUVER OPENING LIMIT OF CONTRACT LOW POINT		STATION STANDARD STEEL		

GENERAL LEGEND

<u>EX</u>	<u>(ISTING</u>	PRO	<u>OPOSED</u>
CONTOUR INDEX CONTOUR WATER SERVICE OVERHEAD ELECTRIC UNDERGROUND ELECTRIC UNDERGROUND TELEPHONE EDGE OF WATER RIGHT—OF WAY EASEMENT CENTERLINE FENCE PROPERTY LINE GUARDRAIL FORCE MAIN GRAVITY SEWER STORM DRAIN	— — — 9 — — — — — — — — — — — — — — — —	CONTOUR INDEX CONTOUR RIGHT—OF—WAY TEMPORARY EASEMENT GATE VALVE HOSE VALVE OR FAUCET CHECK VALVE REDUCER ELBOW UP ELBOW DOWN FENCE FORCE MAIN GAS STORM DRAIN LIMIT OF DISTURBANCE SILT FENCE	9
PRESENTLY ABANDONED STREAM		SUPER SILT FENCE WATER	
DIRT ROAD		DRAIN PROPERTY LINE	
STONE ROAD		TEE	
MACADAM ROAD		WYE	
RAILROAD TRACKS		EXISTING UTILITY TO BE ABANDONED BY CONTRACTOR	
SANITARY SEWER MANHOLE	S	BT CONTRACTOR	
LIGHT POLE		EXISTING UTILITY TO BE ABANDONED BY OTHERS	
UTILITY POLE	Ø	FIRE HYDRANT	
WATER METER	(WM)		<i>⁄</i> ₩
WATER VALVE	WV NO.		
GAS VALVE	GV 		
MAIL BOX	€		
TREE			
WOODS OR BRUSH			
BUILDING STRUCTURES			
BENCH MARK	B.M.		
STANDARD PENETRATION TEST E	BORING B-X		
CONTROL POINT			
GUY POLE	● -		
ITEMS TO BE DEMOLISHED AND REMOVED			

A STATE OF THE PARTY OF THE PAR

NTS WERE PREPARED OR
STATE OF MARYLAND,
DATE: 4/20/2023
EL, KLEPPER & KAHL, LLP
ST PRATT STREET, SUITE 500
MARYLAND 21202 410.728.2900

PROFESSIONAL CERTIFICATION

'CERTIFY THAT THESE DOCUMENTS WERE PREPARE
BY ME, AND THAT I AM A DULY LICENSED PROFES
EER UNDER THE LAWS OF THE STATE OF MARYLAN
CENSE NO. 12420, EXPIRATION DATE: 4/20/2023

NO. DESCRIPTION

BY DATE

SECONI
SECONI
ST. MARY
ABE

ENGINEER DESIGNED BY
RJA MLT

DRAWN BY DATE
DED 4/2021


PROJECT NUMBER
8191SR

DRAWING NUMBER

G-2

SHEET NO. 2 OF 28

3YS — \\balsrv06\v2016\2016\16117_SMCMetCom\CA 2021 — 5:55am ENV.CTB Plot Scale 1=1 P





NOTES:

THE MERIDIAN SOURCE OF THIS TOPOGRAPHIC SURVEY IS BASED ON THE MARYLAND STATE PLANE COORDINATE SYSTEM (NAD83 [1991 HARN]). ALL DISTANCES SHOWN HEREON ARE IN U.S. SURVEY FEET.

ELEVATIONS REFER TO THE NORTH AMERICAN VERTICAL DATUM OF1988 (NAVD88).

BORING LOCATIONS					
DOINT	COORDINATES				
POINT	NORTH	EAST			
SB-1	219.008.37	1.481.058.95			

SB-3 218,943.74 1,481,110.25

1,481,056.50

218,909.87


TRAVERSE SURVEY CONTROL							
TRAV. #	NORTHING	EASTING	ELEV.	DESCRIPTION			
500	218,799.7549	1,481,059.7962	15.34'	MAG NAIL			
501	219,061.9655	1,481,118.8416	8.35'	MAG NAIL			
502	218,996.7436	1,480,961.6648	14.56'	R&C			


	10'	5,'	Q	10'	20'
l"=10'					

		J S
ENGINEER RJA	DESIGNED BY	SMCMetCom\CAD[
DED	DATE 4/2021	
	NUMBER 1SR	2016\2016\16117_

RAWING NUMBER

3YS - \\balsrv06\\\2016\\2016\\2021 - 5:57am ENV.CTB





THESE DOCUMENTS WERE PREPARED OR HAT I AM A DULY LICENSED PROFESSIONAL E LAWS OF THE STATE OF MARYLAND, 20, EXPIRATION DATE: 4/20/2023

RUMMEL, KLEPPER & KAHL, LLP 700 EAST PRATT STREET, SUITE 500

BALTIMORE, MARYLAND 21202 410.728.2900

I HEREBY CERTIFY THAT THESE DOCUMENTS
APPROVED BY ME, AND THAT I AM A DULY L.
ENGINEER UNDER THE LAWS OF THE STA
LICENSE NO. 12420, EXPIRATION DATI

			NO.		
			DESCRIPTION	REVISIONS	
			ВҮ		
			DATE		

SECONDARY CLARIFIER NO. 1 REPLACEMENT
ST. MARY'S COUNTY METROPOLITAN COMMISSION
23121 CAMDEN WAY, CALIFORNIA, MD 20619 (301) 737-7400
PROPOSED
ONDARY CLARIFIER NO. 1, PIPING PLAN AND PRC

ENGINEER DESIGNED BY

RJA MLT

DRAWN BY DATE

DED 4/2021

PROJECT NUMBER

8191SR

C-2
SHEET NO. 4 OF 28





THE MERIDIAN SOURCE OF THIS TOPOGRAPHIC SURVEY IS BASED ON THE MARYLAND STATE PLANE COORDINATE SYSTEM (NAD83 [1991 HARN]). ALL DISTANCES SHOWN HEREON ARE IN U.S. SURVEY FEET.

- ALL STRUCTURES SHOWN ON THIS SHEET ARE EXISTING.
 NO NEW IMPERVIOUS SURFACE IS PROPOSED AS PART OF
 THIS PROJECT, ONLY REPLACEMENT TANKS.
- 2. TOTAL PARCEL AREA IS 34.77 ACRES (TWO PARCELS).
 TOTAL LIMIT OF DISTURBANCE (LOD) AREA IS 0.90 ACRES.

•	PROFESSIO	RTIFY THAT THE WE, AND THAT
---	-----------	--------------------------------


			ВУ	
			DESCRIPTION	SNOISIVE
			ON.	
		00		


<u>LEGEND</u>

LOD	LIMITS OF DISTURBANCE
	PARCEL BOUNDARY
	IDA CRITICAL AREA BOUNDARY

,	MAR	23121
	ENGINEER	DESIGNED BY
		N 41 T

RAE	4/202			
PROJECT NUMBER				
8191SR				






1. SURVEY WAS COMPLETED FOR THE AREA SURROUNDING SECONDARY CLARIFIER NO. 1. ALL FEATURES SHOWN ON THESE PLANS OUTSIDE OF LOD AREA 1 ARE BASED ON GIS DATA RECEIVED FROM ST. MARY'S COUNTY'S GIS DATABASE.


ALL PROPOSED WORK INCLUDES REPLACEMENT OF STRUCTURES IN KIND WITH EXISTING. NO INCREASES IN SITE IMPERVIOUS AREA, AND NO CHANGES IN DRAINAGE PATTERNS ARE EXPECTED POST PROJECT

FOLLOWING INITIAL SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION MUST BE COMPLETED

> (A) THREE (3) CALENDAR DAYS AS TO THE SURFACE OF ÀLL PERIMETER DIKES, SWALES, DITCHES, PERIMETER SLOPES, AND ALL SLOPES STEEPER THAN 3 HORIZONTAL TO 1 VERTICAL (3:1) AND (B) SEVEN (7) CALENDAR DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE

- 2. SEE SEQUENCE OF CONSTRUCTION ON SHEET ES-02.
- TEMPORARY STOCKPILE/STAGING AREA AS SHOWN ON PLANS. CONTRACTOR MAY USE PAVED AREAS ON SITE FOR ADDITIONAL STORAGE AS NEEDED WITH THE APPROVAL OF SITE MANAGER.
- LIMITS OF DISTURBANCE ARE UNDER 1 ACRE, THEREFORE A MARYLAND GENERAL CONSTRUCTION ACTIVITY PERMIT (NOI) IS
- NO PERMANENT STRUCTURES (FENCES, SHEDS, PLAY EQUIPMENT, RETAINING WALLS, ETC.) SHALL BE PERMITTED WITHIN ANY STORM DRAINAGE EASEMENT OR DRAINAGE EASEMENT EITHER SHOWN OR DESCRIBED ON A FINAL PLAT OR EASEMENT PLAT.
- 6. ALL GRADING ON LOT/PARCEL, EITHER BEFORE OR AFTER THE CONSTRUCTION OF A DWELLING, OR APPURTENANCES, SHALL BE THE FULL RESPONSIBILITY OF THE LOT/PARCEL OWNER.





ANY CLEARING, GRADING, CONSTRUCTION OR DEVELOPMENT, OR ALL OF THESE, WILL BE DONE PURSUANT TO THIS PLAN AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF TRAINING AT A MARYLAND DEPT OF ENVIRONMENT APPROVED TRAINING PROGRAM BEFORE BEGINNING THE

> APPROVED DATE

CONSULTANT'S CERTIFICATION

I HEREBY CERTIFY THAT THE PLANS HAVE BEEN DESIGNED IN ACCORDANCE WITH APPROVED EROSION AND SEDIMENT CONTROL ORDINANCES,

DRAWING NUMBER


KCD


ES-01


SHEET NO. 7 OF 28


MARLAY-TAYLOR WATER RECLAMATION FACILIT SECONDARY CLARIFIER NO. 1 REPLACEMENT ST. MARY'S COUNTY METROPOLITAN COMMISSION 3121 CAMDEN WAY, CALIFORNIA, MD 20619 (301) 737-74

ENGINEER DESIGNED BY RAE 4/2021 PROJECT NUMBER 8191SR









 FOR TYPE A, USE NOMINAL 2 INCH X 4 INCH CONSTRUCTION GRADE LUMBER POSTS, DRIVEN 1 FOOT INTO THE GROUND AT EACH CORNER OF THE INLET. PLACE NAIL STRIPS BETWEEN THE POSTS ON THE ENDS OF THE INLET. ASSEMBLE THE TOP PORTION OF THE 2X4 FRAME AS SHOWN. STRETCH ½ INCH GALVANIZED HARDWARE CLOTH TIGHTLY AROUND THE FRAME AND FASTEN SECURELY. FASTEN GEOTEXTILE SECURELY TO THE HARDWARE CLOTH WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND HARDWARE CLOTH A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. THE ENDS OF THE GEOTEXTILE MUST MEET AT A POST, BE OVERLAPPED AND FOLDED, THEN FASTENED TO THE POST. FOR TYPE B, USE 2¾ INCH DIAMETER GALVANIZED STEEL POSTS OF 0.095 INCH WALL THICKNESS AT 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER OF TH STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY TO THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN LINK FENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH THE NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SEDIME! AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET 	 USE WOVEN SLIT FILM GEOTEXTILE AS SPECIFIED IN SECTION H-1 MATERIALS. EXCAVATE COMPLETELY AROUND THE INLET TO A DEPTH OF 18 INCHES BELOW THE NOTCH ELEVATIO FOR TYPE A, USE NOMINAL 2 INCH X 4 INCH CONSTRUCTION GRADE LUMBER POSTS, DRIVEN 1 FOOT INTO THE GROUND AT EACH CORNER OF THE INLET. PLACE NAIL STRIPS BETWEEN THE POSTS ON THE ENDS OF THE INLET. ASSEMBLE THE TOP PORTION OF THE 2X4 FRAME AS SHOWN. STRETCH ½ INCHE GALVANIZED HARDWARE CLOTH WITH THES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND HARDWARE CLOTH A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. THE ENDS OF THE GEOTEXTILE MUST MEET AT A POST, BE OVERLAPPED AND FOLDED, THEN FASTENED TO THE POST. FOR TYPE B, USE 2¾ INCH DIAMETER GALVANIZED STEEL POSTS OF 0.095 INCH WALL THICKNESS AT 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER OF THE STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY TO THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN LINK FENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH THE NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SEDIMEI AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOGGE WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND 	1. USE WOVEN SLIT FILM GEOTEXTILE AS SPECIFIED IN SECTION H-1 MATERIALS. 2. EXCAVATE COMPLETELY AROUND THE INLET TO A DEPTH OF 18 INCHES BELOW THE NOTCH ELEV 3. FOR TYPE A, USE NOMINAL 2 INCH X 4 INCH CONSTRUCTION GRADE LUMBER POSTS, DRIVEN 1 F INTO THE GROUND AT EACH CORNER OF THE INLET. PLACE NAIL STRIPS BETWEEN THE POSTS OF ENDS OF THE INLET. ASSEMBLE THE TOP PORTION OF THE 2X4 FRAME AS SHOWN. STRETCH ½ IN GALVANIZED HARDWARE CLOTH TIGHTLY AROUND THE FRAME AND FASTEN SECURELY. FASTEN GEOTEXTILE SECURELY TO THE HARDWARE CLOTH WITH TIES SPACED EVERY 24 INCHES AT THE AND MID SECTION. EMBED GEOTEXTILE AND HARDWARE CLOTH A MINIMUM OF 18 INCHES BELOW WEIR CREST. THE ENDS OF THE GEOTEXTILE MUST MEET AT A POST, BE OVERLAPPED AND FOLD THEN FASTENED TO THE POST. FOR TYPE B, USE 2¾ INCH DIAMETER GALVANIZED STEEL POSTS OF 0.095 INCH WALL THICKNES 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER O STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE W TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN I FENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. 4. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. 5. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SET AFTER ASCH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLO WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AN		DETAIL E-9-1 STANDARD INLET PROTECTION	STANDARD SYMBOL
 EXCAVATE COMPLETELY AROUND THE INLET TO A DEPTH OF 18 INCHES BELOW THE NOTCH ELEVATION. FOR TYPE A, USE NOMINAL 2 INCH X 4 INCH CONSTRUCTION GRADE LUMBER POSTS, DRIVEN 1 FOOT INTO THE GROUND AT EACH CORNER OF THE INLET. PLACE NAIL STRIPS BETWEEN THE POSTS ON THE ENDS OF THE INLET. ASSEMBLE THE TOP PORTION OF THE 2X4 FRAME AS SHOWN. STRETCH ½ INCH GALVANIZED HARDWARE CLOTH TIGHTLY AROUND THE FRAME AND FASTEN SECURELY. FASTEN GEOTEXTILE SECURELY TO THE HARDWARE CLOTH WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND HARDWARE CLOTH A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. THE ENDS OF THE GEOTEXTILE MUST MEET AT A POST, BE OVERLAPPED AND FOLDED, THEN FASTENED TO THE POST. FOR TYPE B, USE 2¾ INCH DIAMETER GALVANIZED STEEL POSTS OF 0.095 INCH WALL THICKNESS AN 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER OF THE STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY TO THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN LINK FENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH THE NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SEDIMEN AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOGGED WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND 	 EXCAVATE COMPLETELY AROUND THE INLET TO A DEPTH OF 18 INCHES BELOW THE NOTCH ELEVATION. FOR TYPE A, USE NOMINAL 2 INCH X 4 INCH CONSTRUCTION GRADE LUMBER POSTS, DRIVEN 1 FOOT INTO THE GROUND AT EACH CORNER OF THE INLET. PLACE NAIL STRIPS BETWEEN THE POSTS ON THE ENDS OF THE INLET. ASSEMBLE THE TOP PORTION OF THE 2X4 FRAME AS SHOWN. STRETCH ½ INCH GALVANIZED HARDWARE CLOTH TICHTLY AROUND THE FRAME AND FASTEN SECURELY, FASTEN GEOTEXTILE SECURELY TO THE HARDWARE CLOTH WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND HARDWARE CLOTH A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. THE ENDS OF THE GEOTEXTILE MUST MEET AT A POST, BE OVERLAPPED AND FOLDED, THEN FASTENED TO THE POST. FOR TYPE B, USE 2¾ INCH DIAMETER GALVANIZED STEEL POSTS OF 0.095 INCH WALL THICKNESS AN 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER OF TH STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY TO THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN LINK FENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH THE NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SEDIMEN AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOGGED WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND 	 EXCAVATE COMPLETELY AROUND THE INLET TO A DEPTH OF 18 INCHES BELOW THE NOTCH ELEV FOR TYPE A, USE NOMINAL 2 INCH X 4 INCH CONSTRUCTION GRADE LUMBER POSTS, DRIVEN 1 F INTO THE GROUND AT EACH CORNER OF THE INLET. PLACE NAIL STRIPS BETWEEN THE POSTS OI ENDS OF THE INLET. ASSEMBLE THE TOP PORTION OF THE 2X4 FRAME AS SHOWN. STRETCH ½ II GALVANIZED HARDWARE CLOTH TIGHTLY AROUND THE FRAME AND FASTEN SECURELY. FASTEN GEOTEXTILE SECURELY TO THE HARDWARE CLOTH WITH TIES SPACED EVERY 24 INCHES AT THE AND MID SECTION. EMBED GEOTEXTILE AND HARDWARE CLOTH A MINIMUM OF 18 INCHES BELOW WEIR CREST. THE ENDS OF THE GEOTEXTILE MUST MEET AT A POST, BE OVERLAPPED AND FOLD THEN FASTENED TO THE POST. FOR TYPE B, USE 2¾ INCH DIAMETER GALVANIZED STEEL POSTS OF 0.095 INCH WALL THICKNES 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER O STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE WITLES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN I FENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SECURITIES AND COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOWHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND CLORES. 	co	NSTRUCTION SPECIFICATIONS	
GALVANIZED HARDWARE CLOTH TIGHTLY AROUND THE FRAME AND FASTEN SECURELY. FASTEN GEOTEXTILE SECURELY TO THE HARDWARE CLOTH WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND HARDWARE CLOTH A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. THE ENDS OF THE GEOTEXTILE MUST MEET AT A POST, BE OVERLAPPED AND FOLDED, THEN FASTENED TO THE POST. FOR TYPE B, USE 2¾ INCH DIAMETER GALVANIZED STEEL POSTS OF 0.095 INCH WALL THICKNESS AN 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER OF TH STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY TO THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN LINK FENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. 4. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH THE NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. 5. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SEDIMEN AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOGGED WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND	 FOR TYPE A, USE NOMINAL 2 INCH X 4 INCH CONSTRUCTION GRADE LUMBER POSTS, DRIVEN 1 FOOT INTO THE GROUND AT EACH CORNER OF THE INLET. PLACE NAIL STRIPS BETWEEN THE POSTS ON THE ENDS OF THE INLET. ASSEMBLE THE TOP PORTION OF THE 2X4 FRAME AS SHOWN. STRETCH ½ INCH GALVANIZED HARDWARE CLOTH TIGHTLY AROUND THE FRAME AND FASTEN SECURELY. FASTEN GEOTEXTILE SECURELY TO THE HARDWARE CLOTH WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND HARDWARE CLOTH A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. THE ENDS OF THE GEOTEXTILE MUST MEET AT A POST, BE OVERLAPPED AND FOLDED, THEN FASTENED TO THE POST. FOR TYPE B, USE 2¾ INCH DIAMETER GALVANIZED STEEL POSTS OF 0.095 INCH WALL THICKNESS AN 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER OF TH STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY TO THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN LINK FENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH THE NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SEDIMEN AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOGGED WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND 	3. FOR TYPE A, USE NOMINAL 2 INCH X 4 INCH CONSTRUCTION GRADE LUMBER POSTS, DRIVEN 1 FINTO THE GROUND AT EACH CORNER OF THE INLET. PLACE NAIL STRIPS BETWEEN THE POSTS OF ENDS OF THE INLET. ASSEMBLE THE TOP PORTION OF THE 2X4 FRAME AS SHOWN. STRETCH 1/2 IN GALVANIZED HARDWARE CLOTH TIGHTLY AROUND THE FRAME AND FASTEN SECURELY. FASTEN GEOTEXTILE SECURELY TO THE HARDWARE CLOTH WITH TIES SPACED EVERY 24 INCHES AT THE AND MID SECTION. EMBED GEOTEXTILE AND HARDWARE CLOTH A MINIMUM OF 18 INCHES BELOW WEIR CREST. THE ENDS OF THE GEOTEXTILE MUST MEET AT A POST, BE OVERLAPPED AND FOLD THEN FASTENED TO THE POST. FOR TYPE B, USE 2% INCH DIAMETER GALVANIZED STEEL POSTS OF 0.095 INCH WALL THICKNES 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER OF STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE WITHES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN I FENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. 4. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. 5. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SECURITY AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOWHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND CHAIN HIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND CLEAN.	1.	USE WOVEN SLIT FILM GEOTEXTILE AS SPECIFIED IN SECTION H-1 MATERIALS.	
INTO THE GROUND AT EACH CORNER OF THE INLET. PLACE NAIL STRIPS BETWEEN THE POSTS ON THE ENDS OF THE INLET. ASSEMBLE THE TOP PORTION OF THE 2X4 FRAME AS SHOWN. STRETCH ⅓ INCH GALVANIZED HARDWARE CLOTH TIGHTLY AROUND THE FRAME AND FASTEN SECURELY. FASTEN GEOTEXTILE SECURELY TO THE HARDWARE CLOTH WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND HARDWARE CLOTH A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. THE ENDS OF THE GEOTEXTILE MUST MEET AT A POST, BE OVERLAPPED AND FOLDED, THEN FASTENED TO THE POST. FOR TYPE B, USE 2¾ INCH DIAMETER GALVANIZED STEEL POSTS OF 0.095 INCH WALL THICKNESS AN 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER OF TH STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY TO THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN LINK FENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. 4. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH THE NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. 5. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SEDIMENT AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOGGED WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND	INTO THE GROUND AT EACH CORNER OF THE INLET. PLACE NAIL STRIPS BETWEEN THE POSTS ON THE ENDS OF THE INLET. ASSEMBLE THE TOP PORTION OF THE 2X4 FRAME AS SHOWN. STRETCH ⅓ INCH GALVANIZED HARDWARE CLOTH TIGHTLY AROUND THE FRAME AND FASTEN SECURELY. FASTEN GEOTEXTILE SECURELY TO THE HARDWARE CLOTH WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND HARDWARE CLOTH A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. THE ENDS OF THE GEOTEXTILE MUST MEET AT A POST, BE OVERLAPPED AND FOLDED, THEN FASTENED TO THE POST. FOR TYPE B, USE 2¾ INCH DIAMETER GALVANIZED STEEL POSTS OF 0.095 INCH WALL THICKNESS AN 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER OF TH STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY TO THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN LINK FENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. 4. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH THE NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. 5. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SEDIMEN AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOGGED WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND	INTO THE GROUND AT EACH CORNER OF THE INLET. PLACE NAIL STRIPS BETWEEN THE POSTS OF ENDS OF THE INLET. ASSEMBLE THE TOP PORTION OF THE 2X4 FRAME AS SHOWN. STRETCH ½ II GALVANIZED HARDWARE CLOTH TIGHTLY AROUND THE FRAME AND FASTEN SECURELY. FASTEN GEOTEXTILE SECURELY TO THE HARDWARE CLOTH WITH TIES SPACED EVERY 24 INCHES AT THE AND MID SECTION. EMBED GEOTEXTILE AND HARDWARE CLOTH A MINIMUM OF 18 INCHES BELOW WEIR CREST. THE ENDS OF THE GEOTEXTILE MUST MEET AT A POST, BE OVERLAPPED AND FOLD THEN FASTENED TO THE POST. FOR TYPE B, USE 2¾ INCH DIAMETER GALVANIZED STEEL POSTS OF 0.095 INCH WALL THICKNES 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER O STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE WITLES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN I FENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. 4. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. 5. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SET AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOWHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AN	2.	EXCAVATE COMPLETELY AROUND THE INLET TO A DEPTH OF 18 INCHES BELO	W THE NOTCH ELEVATIO
 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER OF THE STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY TO THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN LINK FENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. 4. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH THE NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. 5. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SEDIMEI AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOGGED WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND 	 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER OF TH STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY TO THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN LINK FENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. 4. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH THE NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. 5. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SEDIMEI AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOGGED WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND 	 6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST AT EACH CORNER OF STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN HEIGHT, SECURELY THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CHAIN LINK FENCE WITTES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOTEXTILE AND CHAIN INFENCE A MINIMUM OF 18 INCHES BELOW THE WEIR CREST. 4. BACKFILL AROUND THE INLET IN LOOSE 4 INCH LIFTS AND COMPACT UNTIL SOIL IS LEVEL WITH NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. 5. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SET AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOWHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND 	3.	INTO THE GROUND AT EACH CORNER OF THE INLET. PLACE NAIL STRIPS BETWENDS OF THE INLET. ASSEMBLE THE TOP PORTION OF THE 2X4 FRAME AS SEGALVANIZED HARDWARE CLOTH TIGHTLY AROUND THE FRAME AND FASTEN SEGEOTEXTILE SECURELY TO THE HARDWARE CLOTH WITH TIES SPACED EVERY 2 AND MID SECTION. EMBED GEOTEXTILE AND HARDWARE CLOTH A MINIMUM OF WEIR CREST. THE ENDS OF THE GEOTEXTILE MUST MEET AT A POST, BE OVER	WEEN THE POSTS ON THOWN. STRETCH ½ INCH CURELY. FASTEN 24 INCHES AT THE TOP 18 INCHES BELOW THE
NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. 5. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SEDIMEI AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOGGED WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND	NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. 5. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SEDIMEI AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOGGED WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND	NOTCH ELEVATION ON THE ENDS AND TOP ELEVATION ON THE SIDES. 5. STORM DRAIN INLET PROTECTION REQUIRES FREQUENT MAINTENANCE. REMOVE ACCUMULATED SET AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOWHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AN		6 FOOT LENGTH, DRIVEN A MINIMUM OF 36 INCHES BELOW THE WEIR CREST A STRUCTURE. FASTEN 9 GAUGE OR HEAVIER CHAIN LINK FENCE, 42 INCHES IN THE FENCE POSTS WITH WIRE TIES. FASTEN GEOTEXTILE SECURELY TO THE CITIES SPACED EVERY 24 INCHES AT THE TOP AND MID SECTION. EMBED GEOT	AT EACH CORNER OF TH HEIGHT, SECURELY TO HAIN LINK FENCE WITH
AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOGGEI WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND	AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLOGGEI WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AND	AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLOGGING. IF INLET PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORM EVENT, IT IS CLO WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLACE GEOTEXTILE AN	4.		OIL IS LEVEL WITH THE
			5.	AFTER EACH RAIN EVENT TO MAINTAIN FUNCTION AND AVOID PREMATURE CLO PROTECTION DOES NOT COMPLETELY DRAIN WITHIN 24 HOURS AFTER A STORI WHEN THIS OCCURS, REMOVE ACCUMULATED SEDIMENT AND CLEAN, OR REPLA	OGGING. IF INLET M EVENT, IT IS CLOGGED

MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL

TEMPORARY SEEDING SUMMARY

HARDINESS ZONE: 7B

SEEDING

DATES

3/15-5/31;

5/16-7/31

8/1-9/30

APPLICATION RATE

(LB/AC)

2.2 LB/1000 SF

0.7 LB/1000 SF

96 LB/AC

30 LB/AC

U.S. DEPARTMENT OF AGRICULTURE

SPECIES

FOX TAIL MILLET (Setaria italica)

BARLEY (Hordeum vulgare)

IATURAL RESOURCES CONSERVATION SERVICE

SEQUENCE OF CONSTRUCTION:

- 1. THE CONTRACTOR MUST NOTIFY MISS UTILITY AT 1-800-257-7777 A MINIMUM OF FIVE (5) DAYS PRIOR TO START OF CONSTRUCTION. (5 DAYS)
- 2. PRE-CONSTRUCTION MEETING: NOTIFY ST. MARY'S SOIL CONSERVATION DISTRICT (SCD) AT (301) 475-8402, EXT. 3 AT LEAST FIVE (5) DAYS BEFORE COMMENCING AND LAND DISTURBING ACTIVITY. WORK MAY NOT COMMENCE UNTIL THE PERMITTEE OR THE RESPONSIBLE PERSON HAVE MET ON SITE WITH THE ST. MARY'S SOIL CONSERVATION DISTRICT INSPECTOR TO REVIEW THE APPROVED PLANS. (5 DAYS)
- 2. THE CONTRACTOR SHALL NOTIFY MARYLAND
 DEPARTMENT OF THE ENVIRONMENT (MDE) AT (410)
 537-3510 AT LEAST 48 HOURS PRIOR TO COMMENCING
 CLEARING OR GRADING. (2 DAYS)
- 3. STAKE OUT THE LIMIT OF DISTURBANCE AS SHOWN ON THESE PLANS SO THAT NO WORK WILL OCCUR OUTSIDE THESE AREAS. (DAY 1)
- 4. CLEAR AND GRUB AS NECESSARY FOR INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES. ALL EROSION AND CONTROL MEASURES SHALL BE PLACED PRIOR TO THE START OF CONSTRUCTION AND REMAIN THROUGHOUT. STABILIZE ALL DISTURBED AREAS AT THE END OF EACH WORK DAY. (DAY 1-2)
- 5. INSTALL SILT FENCE OR SUPER SILT FENCE AND STABILIZED CONSTRUCTION ENTRANCE IN THE FOLLOWING LOCATIONS, AS SHOWN ON PLANS: LOD AREA 1, SOUTHEAST OF SECONDARY CLARIFIER NO. 1 ALONG FACILITY DRIVEWAY. LOD AREA 2, NORTH OF PINE HILL RUN ROAD AT PATROL ROAD. (DAY 2)
- 6. GRADE SITE AREA FOR REMOVAL OF TANK, EQUIPMENT, AND ASSOCIATED STRUCTURES. NOTE THAT ANY EXCAVATED MATERIAL MUST GO TO A SITE WITH AN APPROVED SOIL EROSION AND SEDIMENT CONTROL PLAN. CONTRACTOR SHALL HAVE PUMP AND FILTER BAG ON SITE TO DEWATER ALL TRENCHES AS NECESSARY. SEE STANDARD UTILITY NOTES FOLLOWING. (DAY 3-7)
- PREPARE SUBGRADE FOR NEW STRUCTURES AND CONSTRUCT NEW STRUCTURE FOUNDATION AS NEEDED. (DAY 7-14)
- 8. UPON COMPLETION OF ALL TRENCHING AND SITE GRADING, PERMANENTLY SEED AND MULCH WITH A MINIMUM OF 4 INCHES TOPSOIL ALL DISTURBED AREAS FOR STABILIZATION. (DAY 15–16)
- 9. CONTRACTOR SHALL CONTACT THE MARYLAND DEPARTMENT OF THE ENVIRONMENT (MDE) INSPECTOR TO SCHEDULE A FINAL SITE CLOSEOUT REVIEW. (DAY 17)
- 10. AFTER OBTAINING PERMISSION FROM THE MDE INSPECTOR, REMOVE ALL SEDIMENT AND EROSION CONTROL DEVICES. PERMANENTLY STABILIZE ANY AREAS RE-DISTURBED DURING REMOVAL WITH A MINIMUM OF 4 INCHES OF TOPSOIL, SEED, AND MULCH. (DAY 17)

STANDARD UTILITY NOTES:

- 1. REFER TO SHEET C-3 FOR PROPOSED PIPING.
- CONTRACTOR TO ONLY OPEN UP LENGTH OF TRENCH THAT CAN BE CONSTRUCTED AND BACKFILLED IN ONE WORKING DAY IN PAVED AREAS.
- CONTRACTOR TO PLACE EXCAVATED MATERIALS IN A DUMP TRUCK AND HAUL TO AN APPROVED WASTE MATERIAL LOCATION.
- 4. CONTRACTOR TO BACKFILL TRENCH WITH APPROVED MATERIALS AND STABILIZE DISTURBED AREAS THE SAME WORKING DAY.
- 5. IN AREAS WHERE THE CONSTRUCTION TAKES PLACE OUTSIDE OF THE EXISTING ROADBED, CONTRACTOR TO INSTALL SILT FENCE ALONG THE DOWNHILL SIDE OF THE TRENCH BEFORE BEGINNING CONSTRUCTION AND PLACE EXCAVATED MATERIAL FROM THE TRENCH ON THE UPHILL SIDE.
- . IF DEWATERING OF THE TRENCH IS REQUIRED, CONTRACTOR TO DEWATER BY MEANS OF PUMPING THROUGH A FILTER BAG.
- CONTRACTOR TO SWEEP STREETS OF ANY DEBRIS OR SEDIMENTS CAUSED BY CONSTRUCTION OPERATIONS AND DISPOSE OF AT AN APPROVED LOCATION.
- 3. CONTRACTOR TO STABILIZE ALL DISTURBED AREAS WITH SEED & MULCH OR APPROPRIATE STREET REPAIR.

	PERMANENT SEEDING SUMMARY							
	HARDINESS ZONE: 7B SEED MIXTURE: 6			FERTILIZER RATE (10–20–20)				
NO.	SPECIES	APPLICATION RATE (LB/AC)	SEEDING DATES	SEEDING DEPTHS	N	P205	K20	LIME RATE
	Tall Fescue (Lolium arundinaceum)	40	3/1-5/15; 8/15-10/15	1/4-1/2 INCHES				
6	Perennial Ryegrass (Lolium perenne)	25	3/1-5/15; 8/1-10/15	1/4-1/2 INCHES	45 LB/AC (1 LB/ 1000 SF)	90 LB/AC (2 LB/ 1000 SF)	90 LB/AC (2 LB/ 1000 SF)	2 TONS/AC (90 LB/ 1000 SF)
	White Clover (Trifolium repens)	5	3/1-5/15; 8/1-10/15	1/4-1/2 INCHES				

SEEDING DEPTHS

(INCHES)

FERTILIZER RATE

(10-20-20)

436 LB/AC

436 LB/AC

LIME RATE

2 TONS/AC

2 TONS/AC


(10 LB/1000 SF) | (90 LB/1000 SF)

(10 LB/1000 SF) | (90 LB/1000 SF)

2 OF 2

MARYLAND DEPARTMENT OF ENVIRONMENT

WATER MANAGEMENT ADMINISTRATION



PAKED OK ROFESSIONAL SOFEN WILL LIP SUITE 500 ON A LETTER OF THE SOFEN WHILL LIP SUITE 500 ON A LETTER OF THE SOFEN WHILL LIP SUITE 500 ON A LETTER OF THE SOFEN WHILL LIP SUITE 500 ON A LETTER OF THE SOFEN WHILL LIP SOFEN

T THESE DOCUMENTS WERE PREPARED
THAT I AM A DULY LICENSED PROFESS
HE LAWS OF THE STATE OF MARYLANG
120, EXPIRATION DATE: 4/20/2023
RUMMEL, KLEPPER & KAHL, LLP
700 EAST PRATT STREET, SUITE 5
BALTIMORE, MARYLAND 21202 410.72

PPROVED BY ME, AND THAT I ENGINEER UNDER THE LAW LICENSE NO. 12420, EX

DESCRIPTION BY
REVISIONS


AY-TAYLOR WATER RECLAMATION FACILITY
SECONDARY CLARIFIER NO. 1 REPLACEMENT
T. MARY'S COUNTY METROPOLITAN COMMISSION
SAMDEN WAY, CALIFORNIA, MD 20619 (301) 737-7400
EROSION AND SEDIMENT CONTROL
DETAILS


ENGINEER DESIGNED BY
RJA MLT
DRAWN BY DATE
RAE 4/2021
PROJECT NUMBER
8191SR


DRAWING NUMBER

SHEET NO. 8 OF 28

ES-02







PROFESSIONAL CERTIFICATION

TIFY THAT THESE DOCUMENTS WERE PREPARED OR

E, AND THAT I AM A DULY LICENSED PROFESSION

NO. 12420, EXPIRATION DATE: 4/20/2023

RUMMEL, KLEPPER & KAHL, LLP

I HEREBY CERTIFY THAT
APPROVED BY ME, AND TI
ENGINEER UNDER THE
LICENSE NO. 1245

			DATE	
			ВУ	
			DESCRIPTION	REVISIONS
			ON	

- LATLON WATER DECLAMATION FACILITY
CONDARY CLARIFIER NO. 1 REPLACEMENT
JARY'S COUNTY METROPOLITAN COMMISSION
IDEN WAY, CALIFORNIA, MD 20619 (301) 737-7400
OSION AND SEDIMENT CONTROL
DETAILS

ENGINEER DESIGNED BY
RJA MLT
DRAWN BY DATE
RAE 4/2021
PROJECT NUMBER
8191SR

DRAWING NUMBER

ES-03

DESIGN CRITERIA

- A. STRUCTURAL DESIGN SHALL BE IN ACCORDANCE WITH THE GOVERNING PROVISIONS OF THE FOLLOWING CODE, STANDARDS AND SPECIFICATIONS:
- INTERNATIONAL BUILDING CODE (IBC) 2018, INCLUDING MODIFICATIONS MADE BY
- ASCE 7-16 MIN. DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES.
- ACI 318-14 BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE ACI 350-06 CODE REQUIREMENTS FOR ENVIRONMENTAL CONCRETE STRUCTURES. AISC SPECIFICATION FOR STRUCTURAL STEEL BUILDINGS, 16th EDITION.
- AWS D1.1 STRUCTURAL WELDING CODE STEEL.
- B. SUPERIMPOSED DESIGN LOADS:
- LIVE LOADS (MIN): ROOFS, NON-REDUCIBLE: 30 PSF
- STAIRS: 100 PSF
- WALKWAYS AND PLATFORMS: 100 PSF
- GRATING: 100 PSF LIQUIDS 63 PCF
- HANDRAILS AND GUARDS: ALONG THE TOP RAIL APPLY IN ANY DIRECTION, 50 PSF OR 200 LBS POINT LOAD, WHICHEVER RESULTS IN GREATER STRESSES
- DEAD LOADS: CONCRETE: 150 PCF
- STEEL: 490 PCF WATER: 63 PCF
- ASCE 7-10: RISK CATEGORY = III
- WIND LOADS: ULTIMATE DESIGN SPEED: 120 MPH
- NOMINAL DESIGN SPEED: 93 MPH EXPOSURE:
- EDGE DISTANCE (a): 3.0 FEET
- WIND VELOCITY PRESSURE (C&C) ZONE 4: 35.12 PSF
- ZONE 5: 43.37 PSF INTERNAL PRESSURE COEFF.: ± 0.18
- EARTHQUAKE DESIGN DATA: SEISMIC IMPORTANCE FACTOR: le=1.25
- DESIGN SPECTRAL RESPONSE ACCELERATION: Ss=0.127
- DESIGN SPECTRAL RESPONSE ACCELERATION: S1=0.052 DESIGN SPECTRAL RESPONSE ACCELERATION: SdS=0.136
- DESIGN SPECTRAL RESPONSE ACCELERATION: Sd1=0.083
- SOIL SITE CLASSIFICATION: TYPE D SEISMIC DESIGN CATEGORY: B
- ANALYSIS PROCEDURE: EQUIVALENT LATERAL FORCE PROCEDURE SNOW LOADS:
- GROUND SNOW LOAD (Pg): 30 PSF

REQUIREMENTS.

- FLAT ROOF SNOW LOAD (Pf): 25 PSF PLUS DRIFT
- SNOW EXPOSURE FACTOR (Ce): 1.0
- SNOW THERMAL FACTOR (Ct): 1.0 SNOW LOAD IMPORTANCE FACTOR (Is): 1.10
- C. FOUNDATION: SPREAD & WALL FOOTINGS ASSUMED ALLOWABLE BEARING PRESSURE: 2,000 PSF
- (CONTRACTOR TO CONFIRM ASSUMPTION)

ADEQUATELY RESIST ALL CONSTRUCTION LOADS.

- ASSUMED INTERNAL ANGLE OF FRICTION: 28 DEGREES
- ASSUMED UNIT WEIGHT OF SOIL (ABOVE WATER TABLE): 120 PCF
- ASSUMED UNIT WEIGHT OF SOIL (BELOW WATER TABLE): 58 PCF
- ASSUMED AT REST EARTH PRESSURE COEFFICIENT: Ko=0.50 REFER TO EBA ENGINEERING GEOTECHNICAL REPORT DATE SEPT 2019 FOR EARTHWORK

- A. ALL ELEVATIONS ARE REFERENCED TO MSL. SEE CIVIL DWG FOR FINISHED FLOOR ELEV. ALL ELEVATIONS SHOWN ON PLANS ARE REFERENCED TO THIS DATUM UNLESS NOTED
- B. THE GENERAL CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO FABRICATION OR START OF CONSTRUCTION.
- NO STRUCTURAL MEMBER SHALL BE CUT, NOTCHED OR OTHERWISE REDUCED IN STRENGTH
- WITHOUT THE PRIOR NOTIFICATION OF THE STRUCTURAL ENGINEER. D. THE GENERAL CONTRACTOR SHALL COORDINATE ALL OTHER DISCIPLINES FOR ANY ITEMS WHICH
- EFFECT THE STRUCTURAL DRAWINGS. CONTRACTOR SHALL PROVIDE TEMPORARY BRACING, GUY WIRES, ETC., WHERE NECESSARY TO
- **DEMOLITION**
- A. REMOVE EXISTING CONSTRUCTION AS SHOWN ON PLANS. SEE PLANS, SECTIONS, AND DETAILS
- FOR EXTENT OF STRUCTURE TO BE REMOVED. B. EXISTING STRUCTURAL FRAMING SHALL REMAIN UNLESS SPECIFICALLY NOTED ON PLAN TO BE
- REMOVED. C. IF FIELD CONDITIONS DIFFER FROM THOSE SHOWN ON DRAWINGS, NOTIFY ARCHITECT/ENGINEER
- BEFORE PROCEEDING. D. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO EXAMINE THE EXISTING BUILDING DURING THE COURSE OF CONSTRUCTION AND IMMEDIATELY NOTIFY THE ARCHITECT/ENGINEER OF ANY
- AREAS WHERE THE STRUCTURE EXHIBITS DISTRESS OR FAILURE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SATISFY HIMSELF AS TO THE LOCATION OF ANY UTILITIES IN THE IMMEDIATE VICINITY OF CONSTRUCTION SO AS TO PREVENT DAMAGE TO THEM. SHOULD ANY DAMAGE TO SUCH UTILITIES OCCUR THE CONTRACTOR SHALL BE REQUIRED TO

REPAIR SUCH DAMAGE AT HIS OWN EXPENSE AND TO THE SATISFACTION OF THE OWNER.

EXISTING CONSTRUCTION

- A. ALL MEMBER SIZES AND DIMENSIONS AND ELEVATIONS OF EXISTING STRUCTURES SHOWN ON THE DRAWINGS ARE OBTAINED FROM AVAILABLE SOURCES, AND ARE NOT GUARANTEED TO BE TRUE AND EXACT. THE CONTRACTOR SHALL VERIFY THESE DIMENSIONS AND ELEVATIONS BY ACTUAL FIELD MEASUREMENTS PRIOR TO FABRICATION OF ANY MATERIALS AND START OF WORK, AND REPORT ANY DISCREPANCIES TO THE ARCHITECT/ENGINEER.
- THE CONTRACTOR SHALL PROVIDE ALL SHORING, NEEDLING AND BRACING AS REQUIRED TO SUPPORT THE EXISTING STRUCTURE. THE CONTRACTOR SHALL EXAMINE THE EXISTING STRUCTURE TO DETERMINE THE EXTENT OF THE NECESSARY SHORING, NEEDLING. AND UNDERPINNING. THE CAPACITY AND METHOD FOR SHORING AND NEEDLING SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

SUBMISSIONS

IN ADDITION TO SUBMISSIONS AS REQUIRED IN THE SPECIFICATIONS, CONTRACTOR SHALL PROVIDE PLANS, DETAILS AND CALCULATIONS, SIGNED AND SEALED BY A MARYLAND PROFESSIONAL ENGINEER, FOR THE FOLLOWING: HANDRAILS, GRATING, METAL STAIRS, AND PILES.

SUBMITTALS

RECORD SET AT ALL TIMES.

- A. BEFORE SUBMISSION OF SHOP DRAWINGS, THE CONTRACTOR SHALL HAVE DETERMINED AND VERIFIED ALL QUANTITIES, DIMENSIONS, SPECIFIED PERFORMANCE CRITERIA, INSTALLATION REQUIREMENTS, MATERIALS, CATALOG NUMBERS AND SIMILAR DATA AND SHALL HAVE COORDINATED EACH SHOP
- DRAWING WITH OTHER SHOP DRAWINGS AND THE REQUIREMENTS OF THE CONTRACT DOCUMENTS. PRIOR TO SUBMISSIONS, THE CONTRACTOR SHALL STAMP OR PROVIDE A SIMILAR WRITTEN INDICATION THAT THE CONTRACTOR HAS REVIEWED THE SUBMISSION AND IS SATISFIED THE CONTENTS ARE IN COMPLIANCE WITH THE CONTRACT DRAWINGS.
- REPRINTS OF THE CONTRACT DRAWINGS WILL NOT BE ACCEPTED.
- NO DIMENSIONAL INFORMATION MAY BE OBTAINED BY DIRECT SCALING OF THE DRAWINGS.
- ADEQUATE SETS SHALL BE SUBMITTED SO THAT THE ARCHITECT/ENGINEER CAN MAINTAIN ONE

FOUNDATION

- A. ALL FOUNDATIONS SHALL BEAR ON 12" OF #57 STONE OVER UNDISTURBED SOIL WITH AN
- ALLOWABLE BEARING CAPACITY SPECIFIED. B. CONCRETE SHALL NOT BE POURED ON FROZEN GROUND.
- C. PROVIDE SHEETING AS REQUIRED TO SUPPORT LATERAL LOADS DURING EXCAVATION. SEE GEOTECHNICAL REPORT FOR SOIL PROPERTIES.
- D. FILL ALL VOIDS AND REPLACE DISTURBED SOIL WITH LEAN CONCRETE.
- E. REFER TO EBA ENGINEERING GEOTECHNICAL REPORT DATED SEPT. 2019 FOR ADDITIONAL

BACKFILL

DO NOT BACKFILL AGAINST WALLS UNTIL TOP OF WALL IS EITHER TEMPORARILY BRACED OR SUPPORTING SLABS ARE IN PLACE AND HAVE OBTAINED REQUIRED STRENGTH. WHERE BACKFILL IS REQUIRED ON BOTH SIDES OF WALL, BACKFILL BOTH SIDES SIMULTANEOUSLY.

CAST-IN-PLACE REINFORCED CONCRETE

- A. ALL CONCRETE WORK SHALL CONFORM TO ACI-350-06 CODE REQUIREMENTS FOR ENVIRONMENTAL
- CONCRETE STRUCTURES. B. MINIMUM 28 DAY COMPRESSIVE STRENGTH, MAX WATER TO CEMENTITIOUS MATERIAL RATIOS &
- AGGREGATE SIZE: TANK-MAT, SLAB & WALLS: 5,000 PSI, NORMAL WEIGHT, W/C=0.40, #57 AGGREGATE
- OTHER FOUNDATIONS AND WALLS: 4,000 PSI, NORMAL WEIGHT, W/C=0.45, #57 AGGREGATE C. ALL FOUNDATION AND EXPOSED CONCRETE SHALL INCLUDE 5% AIR ENTRAINMENT, UNLESS NOTED
- D. SLUMP 3" MAX FOR FOUNDATIONS & 4" MAX FOR WALLS, PRIOR TO MID RANGE WATER REDUCER
- E. REINFORCING STEEL SHALL CONFORM TO ASTM A-615 GRADE 60. WELDED WIRE FABRIC SHALL CONFORM TO ASTM A-185. F. TERMINATE ALL DISCONTINUED TOP BARS WITH 90 DEGREE STANDARD HOOK UNLESS OTHERWISE
- G. CONTINUOUS BOTTOM BARS SHALL BE SPLICED AT CENTERLINE OF SUPPORTS. CONTINUOUS TOP
- BARS SHALL BE SPLICED AT MIDSPAN. H. AT CHANGES IN DIRECTION OF CONCRETE WALLS, STRIP FOOTINGS, BEAMS, TIE-BEAMS AND BOND
- BEAMS, PROVIDE CORNER BARS AT SAME SIZE AND SPACING AS HORIZONTAL STEEL.
- I. CHAMFER ALL EDGES OF BEAMS, COLUMNS, HAUNCHES, WALLS EQUIPMENT PADS AND SLABS EXPOSED TO VIEW 34" UNLESS OTHERWISE NOTED.
- J. SEE SPECIFICATIONS FOR WATERPROOFING MEMBRANES

REINFORCEMENT

- A. ALL DEVELOPMENT AND SPLICES OF REINFORCEMENT SHALL CONFORM TO THE PROVISIONS OF ACI BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE (ACI 318—LATEST EDITION)
- REINFORCING STEEL SHALL BE DEFORMED BARS OF INTERMEDIATE GRADE NEW BILLET STEEL CONFORMING TO CURRENT REQUIREMENTS OF ASTM A615 GRADE 60. ALL HOOKS SHALL BE STANDARD HOOKS, UNLESS OTHERWISE NOTED.
- C. WELDED WIRE FABRIC (W.W.F.) SHALL CONFORM TO ASTM A185 (LATEST EDITION) D. ALL WELDED WIRE FABRIC SHALL BE SPLICED SO THAT THE OVERLAP OF THE OUTERMOST
- CROSS WIRES OF EACH ADJOINING SHEET IS NOT LESS THAN THE SPACING OF THE CROSS WIRES PLUS TWO INCHES, UNLESS NOTED OTHERWISE. E. REINFORCING BAR SUPPORTS AND SPACERS SHALL CONFORM TO ACI 315-(LATEST EDITION)
- DETAILING MANUAL F. SHOP DRAWINGS SHOWING ALL NECESSARY SECTIONS AND DETAILS FOR THE PROPER POSITIONING OF ALL REINFORCING STEEL SHALL BE SUBMITTED TO THE ARCHITECT/ENGINEER FOR REVIEW BEFORE FABRICATION OR PLACEMENT OF THE STEEL
- G. ALL REINFORCEMENT SHALL HAVE 3" COVER UNLESS OTHERWISE NOTED

WATERPROOFING

FOR LIMITS OF WATERPROOFING FOR EXTERIOR WALLS, SEE STRUCTURAL SECTIONS. MEMBRANE WATERPROOFING SHALL BE AS SPECIFIED IN SECTION 07100.

WATERSTOP

- A. PROVIDE WATERSTOPS IN ALL JOINTS BETWEEN DRY AREAS AND SOURCES OF LIQUID. BETWEEN DRY AND LIQUID AREAS. WATERSTOPS SHALL FORM A CONTINUOUS WATERTIGHT DIAPHRAGM TO
- B. TERMINATE VERTICAL WATERSTOPS THREE INCHES BELOW TOP OF CONCRETE WALLS IN OPEN TANKS. AT THE UNDERSIDE OF ELEVATED FRAMED SLABS THAT ARE ABOVE MAXIMUM WATER SURFACE ELEVATIONS AND ABOVE FINISHED GRADE IN EXTERIOR FOUNDATION WALLS.
- D. INSTALL WATERSTOPS IN CONTINUOUS LENGTHS TO MINIMIZE FIELD SPLICES. E. PROVIDE 2-INCH MINIMUM CLEARANCE BETWEEN WATERSTOPS AND REINFORCING STEEL AND

C. USE FACTORY-MADE CROSSES. TEES AND ELLS AT ALL CORNERS AND INTERSECTIONS.

- OTHER EMBEDDED ITEMS. F. SECURE WATERSTOPS IN POSITION WITH WIRE TIES TO ADJACENT REINFORCING STEEL ON BOTH
- SIDES. ALONG EACH EDGE AS SPECIFIED.
- G. PROVIDE HYDROPHILIC WATERSTOPS ONLY WHERE INDICATED ON THE DRAWINGS. H. PROTECT EXPOSED WATERSTOP FROM DAMAGE.

AUGERED CAST IN PLACE (ACIP) PILES FOUNDATION SYSTEM

- A. EXCAVATION, PREPARATION OF SUBGRADE, AND FOUNDATION CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL REPORT BY EBA ENGINEERING DATED SEPT. 2019.
- FOUNDATIONS. C. THE BOTTOMS OF ALL EXTERIOR GRADE BEAMS SHALL BE 2'-6" MINIMUM BELOW FINISHED GRADE.

B. ALL ORGANIC MATERIALS AND CONSTRUCTION DEBRIS SHALL BE REMOVED IN REGIONS OF ALL

- D. THE CONTRACTOR SHALL SAFEGUARD AND PROTECT ALL EXCAVATIONS. ALL EXCAVATIONS SHALL BE KEPT FREE OF WATER. E. CAST-IN-PLACE CONCRETE PILES SHALL DEVELOP A MINIMUM COMPRESSIVE STRENGTH OF 5,000 PSI
- AT 28 DAYS. STEEL REINFORCING SHALL CONFORM WITH ASTM A615, GRADE 60. F. ACIP PILES SHALL BE 16" DIAMETER AND SHALL HAVE A MINIMUM CAPACITY OF 75 TONS COMPRESSION AND 12 KIPS MIN UPLIFT EACH. LOAD TESTS SHALL BE PERFORMED TO A LOAD OF
- 200% DESIGN LOAD (APPROXIMATELY 150 TONS) AS NOTED IN THE SPECIFICATIONS PRIOR TO THE INSTALLATION OF PRODUCTION PILES. G. TEST PILES SHALL BE DRIVEN BOTH WHERE INDICATED ON THE DRAWINGS AND AS DIRECTED BY THE
- GEOTECHNICAL REPORT AND SPECIFICATIONS. H. ACIP PILES SHALL BE SPACED 10'-0" CENTER TO CENTER MAX. I. THE DEPTH OF THE ACIP PILE SHALL BE DETERMINED BY THE ACIP PILE MANUFACTURER. THE DEPTH
- REQUIRED IS ESTIMATED TO BE 50'-0" BELOW TANK SLAB. J. INSTALLATION OF THE ACIP PILES SHALL BE PERFORMED BY A CONTRACTOR EXPERIENCED WITH ACIP PILES. DURING INSTALLATION.
- K. THE CONTRACTOR SHALL REFER TO THE ARCHITECTURAL, PLUMBING, MECHANICAL, AND ELECTRICAL DRAWINGS FOR ALL LOCATIONS OF TRENCHES, PITS, CONDUITS, ETC. NOT SHOWN ON THE STRUCTURAL DRAWINGS.
- L. THE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN OF THE ACIP PILES. THE PILES SHALL BE DESIGNED BY A PROFESSIONAL ENGINEER. REFER TO THE PLANS, GEOTECHNICAL REPORT AND SPECIFICATION 13631 FOR DESIGN CRITERIA. THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND CALCULATIONS SIGNED AND SEALED BY A MARYLAND PROFESSIONAL ENGINEER PRIOR TO CONSTRUCTION.

STRUCTURAL STEEL

- A. ALL STRUCTURAL STEEL SHALL CONFORM TO THE AISC SPECIFICATIONS FOR THE DESIGN.
- FABRICATION, AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS
 STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING ASTM DESIGNATIONS
- STRUCTURAL STEEL W—SHAPES: A992 HAVING A MINIMUM YIELD STRENGTH OF 50 KSI. • STRUCTURAL STEEL CHANNELS, ANGLES, BARS & PLATES: A36 HAVING A MINIMUM YIELD
- STRENGTH OF 36 KSI. • SQUARE AND RECTANGULAR TUBING: A500, GRADE B HAVING MINIMUM YIELD STRENGTH OF
- 46 KSI. • ROUND PIPE: A53, GRADE B HAVING A MINIMUM YIELD STRENGTH OF 35 KSI.
- BOLTS SHALL CONFORM TO THE FOLLOWING ASTM DESIGNATIONS: HIGH STRENGTH BOLTS: (SS) F593 ANCHOR BOLTS: A307 A36
- D. ALL BOLTS SHALL BE 3/4" DIAMETER, OPEN HOLES 13/16" DIAMETER, UNLESS OTHERWISE SHOWN OR NOTED
- WELDING SHALL BE IN ACCORDANCE WITH AWS STRUCTURAL WELDING CODE (AWS D1.1) AND SHALL BE PERFORMED BY CERTIFIED WELDERS. ALL WELDS SHALL BE MADE WITH AWS A5.1
- ALL SHOP CONNECTIONS SHALL BE HIGH STRENGTH BOLTED OR WELDED. ALL FIELD CONNECTIONS SHALL BE HIGH STRENGTH BOLTED EXCEPT WHERE DETAILS INDICATE
 - NO PENETRATIONS ARE PERMITTED THROUGH STRUCTURAL STEEL MEMBERS UNLESS INDICATED ON STRUCTURAL DRAWINGS OR APPROVED BY ARCHITECT/ENGINEER. APPROVAL OF THE ARCHITECT/ENGINEER SHALL BE MANDATORY FOR THE USE OF CUTTING
- TORCH IN THE FIELD. ALL GROUT UNDER STEEL PLATES SHALL BE NON-SHRINK "PRE-MIX" TYPE AND SHALL HAVE
- A MINIMUM COMPRESSIVE STRENGTH OF 5000 PSI. FOR ALL MISCELLANEOUS STEEL CONSTRUCTION NOT SHOWN ON STRUCTURAL DRAWINGS, SEE
- THE ARCHITECTURAL AND MECHANICAL DRAWINGS. STRUCTURAL STEEL SHALL BE INSPECTED IN THE FIELD BY AN INDEPENDENT TESTING AGENCY
- APPROVED BY THE ARCHITECT AND PAID FOR BY THE CONTRACTOR. ALL STEEL & CONNECTIONS EXPOSED TO WEATHER SHALL BE HOT-DIPPED GALVANIZED
- ACCORDING TO ASTM A123. N. ALL STEEL DESIGNATED AS "STAINLESS STEEL" SHALL BE IN ACCORDANCE WITH ASTM A276,
- O. ALL STRUCTURAL STEEL SHALL BE COATED WITH SYSTEM NUMBER 10 PER SPECIFICATION

ALUMINUM STRUCTURAL SHAPES

- A. ALUMINUM STRUCTURAL SHAPES SHALL BE ASTM B-308, 6061-T6 B. ALLOWABLE TOLERANCES FOR MILLED ALUMINUM STANDARD STRUCTURAL SHAPES SHALL BE IN ACCORDANCE WITH ANSI H35.2. COMPLY WITH THE ALUMINUM DESIGN MANUAL (ADM-1)
- C. ALL RECTANGULAR CUTOUTS IN GRATING SHALL BE MADE TO THE NEXT BEARING BAR BEYOND
- THE PENETRATION WITH A CLEARANCE NOT TO EXCEED BEARING BAR SPACING. D. USE GRATING CLAMPS TO SECURE GRATING TO SUPPORTING MEMBERS. GRATING CLAMPS TO BE A TYPE TO ALLOW FOR EASY REMOVAL OF GRATING.
- ALUMINUM SURFACES IN CONTACT WITH CONCRETE SHALL BE GIVEN A HEAVY COAT OF ALKALI RESISTANT BITUMINOUS PAINT OR OTHER COATING PROVIDING EQUIVALENT PROTECTION BEFORE
- F. CONTRACTOR IS RESPONSIBLE FOR DESIGN OF ALL ALUMINUM STRUCTURES, INCLUDING HANDRAILS, WALKWAYS, GRATING AND STAIRS. CONTRACTOR SHALL SUBMIT SIGNED AND SEALED PLANS. DESIGN SHALL BE IN ACCORDANCE WITH IBC. G. "2" DIAMOND PLATE" SHALL BE ALUMINUM 2" DIAMOND BACK PLANK BY McNICHOLS OR

LEAKAGE TESTING OF LIQUID STRUCTURES

PRIOR TO TESTING, CLEAN EXPOSED SURFACES BY THOROUGHLY HOSING AND REMOVING ALL

APPROVED EQUAL. PLANKS SHALL BE 12" WIDE WITH A CAPACITY OF 250 PSF.

- LOOSENED MATTER AND WASH FROM BOTH SIDES OF STRUCTURE. CONDUCT TESTING BEFORE BACKFILL IS PLACED AGAINST WALLS AND AFTER ALL CONCRETE HAS ATTAINED THE SPECIFIED COMPRESSIVE STRENGTH, BUT NOT LESS THAN 7 DAYS AFTER PLACEMENT
- C. FILL STRUCTURE TO BE SUBJECTED TO LEAKAGE TEST WITH WATER TO THE NORMAL OPERATING
 - LEVEL OR MAXIMUM ANTICIPATED GROUNDWATER LINE, PLUS ONE (1) FOOT. IMMEDIATELY REPAIR ANY VISIBLE LEAKS WHICH APPEAR DURING FILLING BEFORE CONTINUING. AFTER THE STRUCTURE HAS BEEN KEPT FULL FOR 48 HOURS, CLOSE ALL THE VALVES AND GATES TO THE STRUCTURE AND MEASURE THE CHANGE IN WATER SURFACE EACH DAY FOR A FIVE (5) DAY
- E. TEST EVALUATION CRITERIA: 1. THE DROP IN WATER SURFACE IN 24-HOUR PERIOD WITH BASIN FULL IS LESS THAN 1/20 OF 1 PERCENT OF NORMAL VOLUME OF LIQUID CONTAINED IN THE STRUCTURE, AFTER ACCOUNTING FOR EVAPORATION AND PRECIPITATION, AND DAMP SPOTS OR SEEPAGE ARE NOT
- PRESENT ON WALLS OR OTHER AREAS EXPOSED TO VIEW. 2. DETERMINE EVAPORATION BY FLOATING AN EVAPORATION PAN IN STRUCTURE DURING THE TEST

AREAS AND DAMP SPOTS PREVIOUSLY MARKED, AND MAKE NECESSARY REPAIRS, THEN RETEST THE

- F. EXCESSIVE LEAKAGE AND LEAKAGE TEST FAILURE CRITERIA:
- 1. IF THE DROP IN THE WATER SURFACE EXCEEDS THE TEST EVALUATION CRITERIA OR IF DAMP SPOTS OR SEEPAGE IS VISIBLE ON THE SURFACES EXPOSED DURING TESTING. G. IF LEAKAGE IS EXCESSIVE, OR IF DAMP SPOTS AND OBSERVED LEAKAGE IS PRESENT ON EXPOSED SURFACES, DRAIN THE WATER-HOLDING STRUCTURE, EPOXY INJECT ALL CRACKS, PATCH SURFACE
- MAKE ALL REPAIRS AND ADDITIONAL TESTS AT NO ADDITIONAL COST TO THE OWNER.

APPLY SPECIFIED COATINGS ONLY AFTER ACCEPTANCE OF LEAKAGE TEST BY ENGINEER.

ABBREVIATIONS

ADD'L

ALUM

CONC

CONT

DIA

DTL

DWG(S)

EMBED

ΕW

EXP

HD GALV

HORIZ

MANUF

MECH

MRWR

OC

PCF

PSF

REINF

TRANSV

T/WALL

T/RET WALL

TYP

UNO

VIF

w/

W/C

W/IN

W/O

VERT

PLWD

COORD

CENTERLINE DIAMETER PLATE **ADDITIONAL** ABOVE FINISHED FLOOR ALUMINUM **ARCHITECTURAL** BOTTOM BEARING CAST-IN-PLACE CONTROL JOINT CONCRETE MASONRY UNIT CONCRETE CONTINUOUS COORDINATE DEGREE DIAMETER DIMENSION DETAIL DRAWING(S) FACH EACH END EACH FACE ELEVATION EMBED(MENT) EXISTING EACH WAY **EXPANSION** FINISHED FLOOR FOOTING FIELD VERIFY

FIBER REINFORCED PLASTIC GALVANIZED HOT-DIPPED GALVANIZED HORIZONTAL HOLLOW STRUCTURAL SECTION KIPS/SQUARE INCH LONG LEG HORIZONTAL LONGITUDINAL **MANUFACTURE MAXIMUM MECHANICAL** MINIMUM **MISCELLANEOUS** MID RANGE WATER REDUCER MEAN SEAL LEVEL NUMBER ON CENTER POUNDS/CUBIC FOOT

PLYWOOD POUNDS/SQUARE FOOT POUNDS/SQUARE INCH REINFORCEMENT ROOF TOP UNIT SCHEDULE SECTION SQUARE FOOT SIMILAR **SQUARE** STAINLESS STEEL STANDARD TOP & BOTTOM TONGUE & GROOVE TOP OF SLAB INBE ZIFFI **TRANSVERSE** TYPICAL TOP OF WALL

TOP OF RETAINING WALL UNLESS NOTED OTHERWISE VERTICAL VERIFY IN FIELD WITH WATER TO CEMENT RATIO WITHIN **WITHOUT** WELDED WIRE FABRIC

WATER CLARIFIER AY-TAYLOR I SECONDARY C

> **ENGINEER** DESIGNED BY CCC DRAWN BY KAP 4/2021 PROJECT NUMBER 8191SR

DRAWING NUMBER

SHEET NO. 10 OF 28

SPECIAL INSPECTION

A. SPECIAL INSPECTIONS
B. STEEL CONSTRUCTION
C. CONCRETE CONSTRUCTION
D. SOILS
E. DRIVEN PILES DEEP FOUNDATIONS


1704.2 1705.2 1705.3 1705.6 1705.7

SPECIAL INSPECTIONS AND TESTING OF STEEL CONSTRUCTION	DN (IBC 1705	.2)
TYPE	CONTINUOUS SPECIAL INSPECTION	SPECIAL
INSPECTION OF HIGH-STRENGTH BOLTING: A. SNUG-TIGHT JOINTS. B. PRETENSIONED AND SLIP-CRITICAL JOINTS USING TURN-OF-NUT WITH MATCHMARKING OR CALIBRATED WRENCH METHODS OF INSTALLATION.	- -	X
METHODS OF INSTALLATION. C. PRETENSIONED AND SLIP—CRITICAL JOINTS USING TURN—OF—NUT WITHOUT MATCHMARKING OR CALIBRATED WRENCH METHODS OF INSTALLATION.	X	_
D. INSPECTION TASKS PRIOR TO BOLTING — SEE TABLE N5.6-1 IN AISC 360	_	X
E. INSPECTION TASKS DURING BOLTING — SEE TABLE N5.6—2 IN AISC 360	_	Х
F. INSPECTION TASKS AFTER BOLTING — SEE TABLE N5.6—3 IN AISC 360	_	Х
2. MATERIAL VERIFICATION OF STRUCTURAL STEEL AND COLD-FORMED STEEL DECK:		
A. FOR STRUCTURAL STEEL, IDENTIFICATION MARKINGS TO CONFORM TO AISC 360.	_	X
B. FOR OTHER STEEL, IDENTIFICATION MARKINGS TO CONFORM TO ASTM STANDARDS SPECIFIED IN THE APPROVED CONSTRUCTION DOCUMENTS.	_	Х
C. MANUFACTURER'S CERTIFIED TEST REPORTS.	_	Х
3. INSPECTION OF WELDING:A. INSPECTION TASKS PRIOR TO WELDING — SEE TABLE N5.4—1IN AISC 360	_	X
B. INSPECTION TASKS DURING WELDING — SEE TABLE N5.4—2 IN AISC 360	_	X
C. INSPECTION TASKS AFTER WELDING — SEE TABLE N5.4—3 IN AISC 360	_	X
D. FOR RISK CATEGORY III STRUCTURES, PERFORM ULTRASONIC TESTING IN ACCORDANCE WITH AWS D1.1/D1.1M ON ALL CJP GROOVE WELDS IN BUTT, T— AND CORNER JOINTS SUBJECT TO TRANSVERSELY APPLIED TENSION LOADING WITH MATERIALS	_	X
\$\frac{\partial}{6}\tilde{0}0	_	X
F. FOR THERMALLY CUT SURFACES OF ACCESS HOLES, PERFORM MAGNETIC PARTICLE TESTING OR PENETRANT TESTING IN ACCORDANCE WITH AWS D1.1/D1.1M WHERE THE FLANGE THICKNESS OR WEB THICKNESS EXCEEDS 2 INCHES FOR BUILT-UP SHAPES. ANY CRACK SHALL BE DEEMED UNACCEPTABLE.	-	X
4. INSPECTION OF STEEL FRAME JOINT DETAILS FOR COMPLIANCE: A. DETAILS SUCH AS BRACING AND STIFFENING. B. MEMBER LOCATIONS.	_ _ _	X
C. APPLICATION OF JOINT DETAILS AT EACH CONNECTION. 5. INSPECTION OF STEEL ELEMENTS OF COMPOSITE CONSTRUCTION PRIOR TO CONCRETE PLACEMENT — SEE TABLE N6.1 IN AISC 360		X

SPECIAL INSPECTIONS AND TESTING OF CONCRETE CONSTRUC	TION (IBC 170	05.3)
TYPE	CONTINUOUS SPECIAL INSPECTION	SPECIAL
1. INSPECT REINFORCEMENT, INCLUDING PRESTRESSING TENDONS, AND VERIFY PLACEMENT.	_	Х
2. REINFORCING BAR WELDING: A. VERIFY WELDABILITY OF REINFORCING BARS OTHER THAN ASTM A706; B. INSPECT SINGLE PASS FILLET WELDS, MAXIMUM 5/6"; AND C. INSPECT ALL OTHER WELDS.	_ _ X	X X -
3. INSPECT ANCHORS CAST IN CONCRETE.	_	X
4. INSPECT ANCHORS POST—INSTALLED IN HARDENED CONCRETE MEMBERS. A. ADHESIVE ANCHORS INSTALLED IN HORIZONTALLY OR UPWARDLY INCLINED ORIENTATIONS TO RESIST SUSTAINED TENSION LOADS. B. MECHANICAL ANCHORS AND ADHESIVE ANCHORS NOT DEFINED	X -	- X
IN 4.a. 5. VERIFY USE OF REQUIRED DESIGN MIX.	_	X
6. PRIOR TO CONCRETE PLACEMENT, FABRICATE SPECIMENS FOR STRENGTH TESTS, PERFORM SLUMP AND AIR CONTENT TESTS, AND DETERMINE THE TEMPERATURE OF THE CONCRETE.	Х	_
7. INSPECT CONCRETE AND SHOTCRETE PLACEMENT FOR PROPER APPLICATION TECHNIQUES.	X	_
8. VERIFY MAINTENANCE OF SPECIFIED CURING TEMPERATURE AND TECHNIQUES.	_	Х
9. INSPECT PRESTRESSED CONCRETE FOR: A. APPLICATION OF PRESTRESSING FORCES, AND B. GROUTING OF BONDED PRESTRESSING TENDONS.	X	_ _
10. INSPECT ERECTION OF PRECAST CONCRETE MEMBERS.	_	X
11. VERIFY IN—SITU CONCRETE STRENGTH, PRIOR TO STRESSING OF TENDONS IN POST—TENSIONED CONCRETE AND PRIOR TO REMOVAL OF SHORES AND FORMS FROM BEAMS AND STRUCTURAL SLABS.	_	X
12. INSPECT FORMWORK FOR SHAPE, LOCATION AND DIMENSIONS OF THE CONCRETE MEMBER BEING FORMED.	_	Х


SPECIAL INSPECTIONS AND TESTING OF SOILS (IBC	1705.6)	
TYPE	CONTINUOUS SPECIAL INSPECTION	PERIODIC SPECIAL INSPECTION
1. VERIFY MATERIALS BELOW SHALLOW FOUNDATIONS ARE ADEQUATE TO ACHIEVE THE DESIGN BEARING CAPACITY.	_	Х
2. VERIFY EXCAVATIONS ARE EXTENDED TO PROPER DEPTH AND HAVE REACHED PROPER MATERIAL.	_	X
3. PERFORM CLASSIFICATION AND TESTING OF COMPACTED FILL MATERIALS.	_	Х
4. VERIFY USE OF PROPER MATERIALS, DENSITIES AND LIFT THICKNESSES DURING PLACEMENT AND COMPACTION OF COMPACTED FILL.	X	_
5. PRIOR TO PLACEMENT OF COMPACTED FILL, INSPECT SUBGRADE AND VERIFY THAT SITE HAS BEEN PREPARED PROPERLY.	_	Х


	TYPE	CONTINUOUS SPECIAL INSPECTION	SPECIAL
1.	VERIFY ELEMENT MATERIALS, SIZES AND LENGTHS COMPLY WITH THE REQUIREMENTS.	X	-
2.	DETERMINE CAPACITIES OF TEST ELEMENTS AND CONDUCT ADDITIONAL LOAD TESTS, AS REQUIRED.	×	_
3.	INSPECT DRIVING OPERATIONS AND MAINTAIN COMPLETE AND ACCURATE RECORDS FOR EACH ELEMENT.	×	_
4.	VERIFY PLACEMENT LOCATIONS AND PLUMBNESS, CONFIRM TYPE AND SIZE OF HAMMER, RECORD NUMBER OF BLOWS PER FOOT OF PENETRATION, DETERMINE REQUIRED PENETRATIONS TO ACHIEVE DESIGN CAPACITY, RECORD TIP AND BUTT ELEVATIONS AND DOCUMENT ANY DAMAGE TO FOUNDATION ELEMENT.	X	-
5.	FOR STEEL ELEMENTS, PERFORM ADDITIONAL SPECIAL INSPECTIONS IN ACCORDANCE WITH SECTION 1705.2.	_	_
6.	FOR CONCRETE ELEMENTS AND CONCRETE—FILLED ELEMENTS, PERFORM TESTS AND ADDITIONAL SPECIAL INSPECTIONS IN ACCORDANCE WITH SECTION 1705.3.	1	1
7.	FOR SPECIALTY ELEMENTS, PERFORM ADDITIONAL SPECIAL INSPECTIONS AS DETERMINED BY THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE.	_	_



		•					
					DATE		
					ВУ		
					DESCRIPTION	REVISIONS	
					NO.		
ΥTI	-		(-/400			FRIICTIIRAI dwa

ENGINEER DESIGNED BY
RLA CCC
DRAWN BY DATE
KAP 4/2021
PROJECT NUMBER
8191SR





MARLAY-TAYLOR WATER RECLAMATION FACILITY

SECONDARY CLARIFIER NO. 1 REPLACEMENT

ST. MARY'S COUNTY METROPOLITAN COMMISSION

23121 CAMDEN WAY, CALIFORNIA, MD 20619 (301) 737-7400


PILE LOCATION AND GRADE BEAM LAYOUT

0 4'-0" 8'-0" 12 SCALE 3/16"=1'-0" AT ORIGINAL SIZE 8191SR

DRAWING NUMBER


S-3


KAP



4/2021

DRAWING NUMBER






					NO.	
MARLAY-TAYLOR WATER RECLAMATION FACILITY	SECONDARY CLARIFIER NO. 1 REPLACEMENT	ST. MARY'S COUNTY METROPOLITAN COMMISSION	23121 CAMDEN WAY, CALIFORNIA, MD 20619 (301) 737-7400	S II V LAG GIVV IVV IG		
II E	NGIN	EER	DE	SIGN	ED B	Υ


8191SR

DRAWING NUMBER

SCALE 3/16"=1'-0" AT ORIGINAL SIZE




4/2021




ENGINEER DESIGNED BY 4/2021 PROJECT NUMBER 8191SR

DRAWING NUMBER S-7SHEET NO. 16 OF 28

SCALE 3/8"=1'-0" AT ORIGINAL SIZE





MARLAY-TAYLOR WATER RECLAMATION FACILITY
SECONDARY CLARIFIER NO. 1 REPLACEMENT
ST. MARY'S COUNTY METROPOLITAN COMMISSION
23121 CAMDEN WAY, CALIFORNIA, MD 20619 (301) 737-7400

SECTIONS AND DETAILS

1'-0" 2'-0" 3'-0" DRAWING NUMBER

SCALE 3/4"=1'-0" AT ORIGINAL SIZE

2'-0" 4'-0" 6'-0"

S—8


SCALE 3/8"=1'-0" AT ORIGINAL SIZE

ALBRECHT ENGINEERING INC

S—8
SHEET NO. 17 OF 28


4/2021


DRAWN BY




CCC 4/2021 PROJECT NUMBER 8191SR

DRAWING NUMBER S-9








ENGINEER DESIGNED BY 4/2021 PROJECT NUMBER 8191SR

DRAWING NUMBER






ENGINEER DESIGNED BY DED 4/2021 PROJECT NUMBER 8191SR

> DRAWING NUMBER PM-2

SHEET NO. 22 OF 28

1. EXISTING CLARIFIER MECHANISM TO BE MODIFIED FOR DEEPER TANK AND INSTALLED PER SPECIFICATIONS.

2. NEW RAS PUMP STATION NOT SHOWN.




1/4" GAP /


FACE OF


TOP OF CONCRETE

NEW REMOVABLE GRATING, BY MANUFACTURER NEW 48" PRECAST CIRCULAR TANK— T/W EL. 11.35 NEW ROADWAY BOX — 3'-2" 777777777 **** 6" SCUM LINE FROM CLARIFIER TROUGH EST. INV. EL. 4.50 6" PLUG VALVE 6" SCUM LINE CONNECTION TO EXISTING 6" SCUM LINE. CONTRACTOR TO CONFIRM INVERT ELEVATION OF EXISTING SCUM LINE DURING DEMOLITION.

NOTE: EXISTING PIPING ELEVATION UNKNOWN. CONTRACTOR TO MAKE BOTTOM OF TANK 2 FEET BELOW INVERT OF SCUM LINE.







ELECTRICAL ABBREVIATIONS

A – AMPERES

A.F.F. – ABOVE FINISHED FLOOR

ATS - AUTOMATIC TRANSFER SWITCH

C – CONDUIT

G.F.I. - GROUND FAULT INTERUPTER

GRD. – GROUND

HP - HORSEPOWER

KW – KILOWATT

MCP - MOTOR CIRCUIT PROTECTOR

SOLID NEUTRAL

P – POLE

PH - PHASE

PR. – PAIR

SHLD. – SHIELDED

T-M - THERMAL MAGNETIC

TYP. – TYPICAL

V – VOLTS

W - WIRE, WATT

WP - WEATHERPROOF

XFMR - TRANSFORMER

ELECTRICAL SYMBOL SCHEDULE

LED LIGHT FIXTURE

→ INCANDESCENT LIGHT FIXTURE

→ 20A-120V SINGLE RECEPTACLE

✓5 – MOTOR (NUMBER INDICATES HP)

JUNCTION BOX

THERMOSTAT

T TRANSFORMER

S - SINGLE POLE SWITCH

- HOME RUN TO PANEL

- WIRING CONCEALED IN CONDUIT

CIRCUIT BREAKER

→ → THERMAL OVERLOAD

(1CR) - CONTROL RELAY

ELECTRICAL DUCT BANK

DUCT BANK CROSS SECTION


— G — - #4/0 COPPER GROUND RING


GENERAL ELECTRICAL NOTES (APPLICABLE TO ALL DRAWINGS)

- EXISTING EQUIPMENT IS SHOWN IN A LIGHT WEIGHT AND IDENTIFIED WITH SLANTED TEXT. NEW EQUIPMENT AND WIRING IS SHOWN BOLD.
- 2. CONTRACTOR SHALL COORDINATE THE EXACT LOCATION OF ALL UNDERGROUND CONDUITS AND DUCT BANKS TO AVOID INTERFERENCES WITH UNDERGROUND PIPING AND UTILITIES.
- 3. ALL FASTENERS AND MOUNTING HARDWARE USED FOR THE INSTALLATION OF ALL ELECTRICAL ITEMS SHALL BE 316 STAINLESS STEEL.
- 4. CONTRACTOR SHALL FURNISH AND INSTALL A SEPARATE INSULATED GROUND CONDUCTOR IN ALL CONDUITS. ALL GROUND CONDUCTORS SHALL BE #12 UNLESS NOTED OTHERWISE ON DRAWINGS.

NOTES

1. REMOVE EXISTING ELECTRICAL DUCT BANKS TO SECONDARY CLARIFIER NO. 1 FOR CONSTRUCTION OF NEW SECONDARY CLARIFIER AND INSTALLATION OF A NEW MANHOLE. ELECTRICAL DUCT BANKS WERE INSTALLED IN CONTRACT NO. 8-26-S.







DTB SMJ 4/2021


PROJECT NUMBER

8191SR

DRAWING NUMBER

E-1

SHEET NO. 23 OF 28




ELECTRICAL SITE PLAN

1"=40'

NOTES


1. CONTRACTOR SHALL EXCAVATE A TEST PIT TO CONFIRM EXACT LOCATION OF EXISTING DUCT BANK TO SECONDARY CLARIFIER NO. 1.



MANHOLE NOTES

- MANHOLE LID SHALL BE STAMPED "ELECTRIC". INSTALL A PLASTIC INSERT IN MANHOLE LID.
- 2. PROVIDE A FIBERGLASS ACCESS LADDER IN THE MANHOLE.
- 3. ALL DUCT BANK ENTRIES INTO THE MANHOLE SHALL BE SEALED WATERTIGHT.


PLAN VIEW




SECTION

TYPICAL MANHOLE DETAIL

NO SCALE



DUCT BANK ©
CONNECTION DETAIL
NO SCALE



CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR SY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ER UNDER THE LAWS OF THE STATE OF MARYLAND, NSE NO. 50811, EXPIRATION DATE: 6/14/2023.

RUMMEL, KLEPPER & KAHL, LLP 700 EAST PRATT STREET, SUITE 500 BALTIMORE, MARYLAND 21202, 410.728.2900

			BY DATE		
			DESCRIPTION	REVISIONS	
			NO.		


SECONDARY CLARIFIER NO. 1 REPLACEM
ST. MARY'S COUNTY METROPOLITAN COMIN
23121 CAMDEN WAY, CALIFORNIA, MD 20619 (30
PROPOSED ELECTRICAL SITE F
AND SITE DETAILS

ENGINEER DESIGNED BY				
DTB	SMJ			
DRAWN BY DATE				
SMJ	4/2021			
PROJECT NUMBER				
8191SR				

DRAWING NUMBER

E-2

MBER



DUCT BANK CONDUIT SCHEDULE							
CONDUIT NO.	CONDUIT SIZE	CONDUIT MATERIAL	FROM	ТО	VIA DUCT BANKS	CIRCUITS	
1	2"	PVC	SECONDARY CLARIFIER NO. 1 PULL BOX	EXISTING 2"C IN DUCT BANK (V)	A©	SECONDARY CLARIFIER DRIVE MOTOR FEEDER FROM MCC-B	
2	2"	PVC	SECONDARY CLARIFIER NO. 1 PULL BOX	EXISTING 2"C IN DUCT BANK (V)	AC	120V CONTROL WIRING TO MCC-B	
3	2"	PVC	SECONDARY CLARIFIER NO. 1 PULL BOX	EXISTING 2"C IN DUCT BANK (V)	AC	SPARE	
4	3"	PVC	RAS PUMP ELECTRICAL BACKBOARD	EXISTING 3"C IN DUCT BANK (V)	BC	RAS PUMP NO. 1 MOTOR FEEDER FROM MCC-B	
5	3"	PVC	RAS PUMP ELECTRICAL BACKBOARD	EXISTING 3"C IN DUCT BANK (V)	BC	RAS PUMP NO. 2 MOTOR FEEDER FROM MCC-B	
6	2"	PVC	RAS PUMP ELECTRICAL BACKBOARD	EXISTING 2"C IN DUCT BANK (V)	BC	120V CONTROL WIRING TO MCC-B	

IIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIII
INTA POLITY BOX
GER GER
PRO
NOVAL EVONIL
D. Timely Balling

 ATER RECLAMATION FACILITY
 PRO

 RIFIER NO. 1 REPLACEMENT
 1 HEREBY CERTIFY THAT PROVIDED BY ME, AND ENGINEER UNDER LICENSE NO. 5

 METROPOLITAN COMMISSION
 1 HEREBY CERTIFY THAT PROVIDED BY ME, AND ENGINEER UNDER LICENSE NO. 5

 IFORNIA, MD 20619 (301) 737-7400
 NO.
 DESCRIPTION


 X CROSS SECTIONS
 NO.
 DATE

 ADUIT SCHEDULE
 DATE

ENGINEER	DESIGNED BY				
DTB	SMJ				
DRAWN BY	DATE				
SMJ	4/2021				
PROJECT NUMBER					
8191SR					

DRAWING NUMBER

SHEET NO. 25 OF





NOTES

1. WHERE EQUIPMENT IS SHOWN BEING

REMOVED OR RELOCATED, REMOVE ALL ASSOCIATED WIRE AND EXPOSED CONDUIT.

2. REMOVE EXISTING SECONDARY CLARIFIER

SECONDARY CLARIFIER BRIDGE. REMOVE

3. REMOVE EXISTING RAS PUMP DISCONNECT

4. REMOVE EXISTING SCUM TROUGH SPRAY

5. REMOVE PULL BOX AND SLUDGE BLANKET LEVEL TRANSMITTER AND BACKBOARD IN

BACKBOARD IN ITS ENTIRETY.

ITS ENTIRETY.

WATER CONTROL PANEL AND ELECTRICAL

EXISTING BACKBOARDS IN THEIR ENTIRETY.


SWITCHES AND SEAL LEAK RELAY PANEL AND RE-INSTALL ON NEW ELECTRICAL BACKBOARD.


REMOVE EXISTING BACKBOARD IN ITS ENTIRETY.

DISCONNECT SWITCH AND CONTROL PANEL AND RE-INSTALL ON THE NEW

SMJ 8191SR


E-4






SECONDARY CLARIFIER NO. 1 DRIVE ELECTRICAL BACKBOARD DETAIL

NO SCALE



RAS PUMPS ELECTRICAL BACKBOARD DETAIL NO SCALE




MARLAY-TAYLOR WATER RECLAMATION FACILITY SECONDARY CLARIFIER NO. 1 REPLACEMENT ST. MARY'S COUNTY METROPOLITAN COMMISSION 3121 CAMDEN WAY, CALIFORNIA, MD 20619 (301) 737-740

ENGINEER DESIGNED BY DTB SMJ DRAWN BY SMJ 4/2021 PROJECT NUMBER 8191SR


DRAWING NUMBER E-5

SHEET NO. 27 OF 28



BLOWER/CHEMICAL BUILDING

ELECTRICAL PLAN




EXISTING MCC-B ELEVATION MODIFICATIONS

NOTES


- 1. THE EXISTING RAS PUMP BACKBOARD SHALL BE REMOVED. THE EXISTING RAS PUMP DISCONNECT SWITCHES AND SEAL LEAK RELAY PANEL SHALL BE RELOCATED TO A NEW BACKBOARD ADJACENT TO THE RELOCATED RAS PUMPS.
- 2. THE EXISTING SECONDARY CLARIFIER NO. 1
 DISCONNECT SWITCH AND CONTROL PANEL
 SHALL BE REMOVED FROM THE EXISTING
 CLARIFIER BRIDGE AND RELOCATED TO THE
 BRIDGE AFTER THE BRIDGE IS INSTALLED IN
 THE NEW SECONDARY CLARIFIER.

WIRING LEGEND

- 3#1, #6 GRD. RUN IN DUCT BANK CONDUIT NO. 4 AND EXISTING 3"C
- 2 16#14, #12 GRD. CONTROL WIRING. RUN IN DUCT BANK CONDUIT NO. 6 AND EXISTING 2" CONDUITS
- 3 3#1, #6 GRD. RUN IN DUCT BANK CONDUIT NO. 5 AND EXISTING 3"C
- 4 16#14, #12 GRD. CONTROL WIRING. RUN IN DUCT BANK CONDUIT NO. 2 AND EXISTING 2" CONDUITS
- 5 3#12, #12 GRD. RUN IN DUCT BANK CONDUIT NO. 1 AND EXISTING 2"C



EXISTING MCC-B MODIFICATIONS
ONE-LINE DIAGRAM



PROPOSED MCC-B MODIFICATIONS
ONE-LINE DIAGRAM

SO THE BOOK THE SOUNT THE

SE DOCUMENTS WERE PREFARED OR I AM A DULY LICENSED PROFESSIONAL WS OF THE STATE OF MARYLAND, EXPIRATION DATE: 6/14/2023.

RUMMEL, KLEPPER & KAHL, LLP 700 EAST PRATT STREET, SUITE 500

BALTIMORE, MARYLAND 21202 410.728.2900

CONTRICTION MANAGERS | PLANNERS | SCIENTISTS

I HEREBY CERTIFY THAT THESE DOCUMEN APPROVED BY ME, AND THAT I AM A DUL) ENGINEER UNDER THE LAWS OF THE S LICENSE NO. 50811 , EXPIRATION L

NO. DESCRIPTION BY IT

MARLAY-TAYLOR WATER RECLAMATION FACILITY
SECONDARY CLARIFIER NO. 1 REPLACEMENT
ST. MARY'S COUNTY METROPOLITAN COMMISSION
23121 CAMDEN WAY, CALIFORNIA, MD 20619 (301) 737-74C
BLOWER/CHEMICAL BUILDING
ELECTRICAL PLAN AND ONE-LINE DIAGRAMS

ENGINEER DESIGNED BY
DTB SMJ

DRAWN BY DATE
SMJ 4/2021

PROJECT NUMBER
8191SR

E-6

SHEET NO. 28 OF 28